SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1904, by Munn & Co.]

Vol. XCI.—No. 23.
ESTABLISHED 1845.

NEW YORK, DECEMBER 3, 1904.

8 CENTS A COPY
$3.00 A YEAR.



Copyright, 1904, by Munn & Co.

Henri Becquerel

[See page 385.]



SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO., - - Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

TERMS TO SUBSCRIBERS

One copy, one year for the United States, Canada, or Mexico $3.00
One copy, one year, to any foreign country, postage prepaid. £0 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845) ..... $3.00 a year
Scientific American Supplement (Established 1876) ..... 5.00 "
Scientific American Building Monthly (Established 1885) ..... 2.50 "
Scientific American Export Edition (Established 1878) ..... 3.00 "

The combined subscription rates and rates to foreign countries will be furnished upon application.
Remit by postal or express money order, or by bank draft or check.
MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, DECEMBER 3, 1904.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are *sharp*, the articles *short*, and the facts *authentic*, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

PRODUCTION AND POPULATION.

We could not ask for stronger evidence of the increasing prosperity of the country than is afforded by the last publication of the Bureau of Statistics, embodying the annual review of the foreign commerce of the United States. It contains figures which show the progress in production and consumption, in the United States, of coal, iron, and petroleum. The increase is really astonishing, particularly when it is borne in mind that it has been far more rapid—five times more rapid, in fact—than the increase of population. Thus, in 1894, the production of coal was 152,447,791 tons; in 1903, it was 319,068,229 tons, an increase of over 100 per cent. In 1894, the production of pig iron was 7,000,000 tons; in 1903, it had risen to 18,000,000 tons, an increase of over 150 per cent. The production of petroleum rose from 2,072,469,672 gallons in 1894 to 4,219,374,154 gallons in 1903, an increase of over 100 per cent. Now, the increase of population in the United States is estimated as not more between the years 1894 and 1903, than 21 per cent, so that the production of these important materials of industry has increased from five to seven times faster than would naturally be called for by the growth of population. It should be noted, moreover, that during this increase, the exports of coal have been nominal, while the exports of petroleum have slightly decreased; showing that the home consumption is growing in a ratio proportionate to the increased production.

GAS TURBINES.

It was inevitable that the success of the steam turbine should lead to an investigation of the problem of the gas turbine; for it is natural to argue broadly that the results obtained with one gas will be obtained with any other, unless indeed some radical difficulties inherent in the gas or in the mechanism employed for its expansion should be found to stand in the way. The prospects for the early development of the gas turbine were discussed recently in a paper read before the British Institute of Mechanical Engineers, and, according to the author, those prospects are not very bright. Of course, one of the chief difficulties is the high temperature of the gas, which necessitates, if the temperature is to be reduced to a degree that is not injurious to the cylinder, the carrying away of a large amount of heat by the cooling water. If it were attempted to dispense with cooling water, or to use only as much as would cause a moderate reduction of the temperature, the rotating parts of the turbine would have to run red hot, and there is no material known to the engineering art to-day that would hold together at such high temperature, if subjected to the great centrifugal forces that would be developed.

POWER OF OCEAN WAVES.

At the International Engineering Congress, recently held at St. Louis, some unusual figures were given on the subject of the height and power of ocean waves, particularly as regards their effect upon harbor works. In the course of a paper dealing with the new Dover harbor, it was stated that since these works have been in progress, no wave of a greater height than 15 feet has been recorded—a fact which will be very surprising to those who have experienced the miseries of the Dover-Calais passage. The fact is the more remarkable because at the entrance to the Tyne, waves from 35 feet to 40 feet high have been measured, and the last-named height has also been observed at Peterhead. In dwelling upon the necessity for what are known as spending-beaches and wave-traps, for dissipating and controlling wave action, it was stated that the depth to which the latter extends is now known to be much greater than was once commonly supposed. Proof of this is shown by the fact that lobster pots placed in from 120 to 180 feet of water, have been found to be filled with sand and shingle after a heavy gale; moreover, sand had been found deposited after a heavy gale in the gallery of the Bishop Rock lighthouse, the latter being 120 feet above the water, and the depth of the water at that point 150 feet. That the water, even at considerable depths, must be moving during a gale with great momentum, is shown by the fact that at the Peterhead breakwater blocks weighing 41 tons and located over 36 feet below spring tide low-water, were displaced during a storm, while a section of the breakwater weighing 3,300 tons was moved bodily for a few inches without the brickwork being dislocated.

ELECTRIC TRACTION FOR TRUNK ROADS.

The successful test of the first of the electric locomotives that are being built for the main line of the New York Central Railroad, marks a definite step toward the day when trunk-line passenger service will be worked by electrical traction. The locomotive did everything that had been expected of it, hauling its test loads with that rate of acceleration which is one of the chief advantages of the electric motor, whether applied to the locomotive or directly to the cars. The success of the New York Central installation, of which no reasonable doubt can be entertained, will be followed by the electrifying of similar stretches of steam roads, on which the traffic is sufficiently dense and heavy to warrant the change. There were special conditions connected with the New York Central service which rendered the use of the electric locomotive desirable; but when such systems as those of the Pennsylvania between New York and Washington or Pittsburg, or of the New Haven road between New York and Boston, come to be electrically equipped, we think it is altogether probable that the Sprague system of multiple control will be adopted, the electric locomotive being dispensed with. This implies a better distribution of the weight and power throughout the train, greater smoothness of running, and, of course, less wear and tear upon the track and bridges.

SUBWAY RESULTS.

The New York Subway has been in operation for a sufficient time to enable the public to realize how far its performance comes up to its high promise. In spite of a pretty liberal bombardment by the crank and the faddist, carried on from the vantage ground of the correspondence columns of the local press, there is little doubt that New York city is greatly pleased with its new system of transportation. The feature that appeals most strongly to the downtown business man and the theater-goer is the system of express trains, in which the operating company has fully redeemed its promise of a fifteen-minute service to Harlem. These trains have hitherto been run under a four-minute headway, but now that the east side branch of the road has been opened, the expresses will be run under a two-minute headway as far as the junction at Ninety-sixth Street, and a four-minute headway upon the two branches of the road from that point to their respective termini. There are two features in particular that mark the road as constructed on the most up-to-date practice in electrical traction. One is the remarkably rapid acceleration, which amounts to 1.25 miles per second, and the other is the splendid condition of the track. The combination of 100-pound rails with a tie-plate on every tie, and broken stone ballast laid on a concrete foundation, provides a remarkably smooth track, in which both surface and alignment are all that could be asked. Another feature that contributes to comfortable riding is that the curves are "spiraled," that is to say, the track runs from the tangent to the maximum curvature in a parabola, the change of direction being so gradual that the jolt which usually accompanies the entrance of a train upon a curve is entirely removed. The express train service is undoubtedly the most valuable feature of the new Subway; and it augurs well for the future service of the system that Mr. Belmont has expressed the conviction that the Subway was intended primarily to provide service of this nature, and that the more completely it is given up to express trains, the more fully will it meet the needs of this great and populous city.

A UNITED STATES WARSHIP ON TRIAL.

In the life of a warship there is no event—always excepting, of course, the day of battle—around which so great interest, both sentimental and practical, centers as her trial trip; for rightly or wrongly, the world has fallen into the habit of placing the speed of a warship as first in value of the many separate elements that go to make up the sum total of her efficiency.

It was, therefore, with no small amount of interest that the editor recently boarded the United States armored cruiser "Pennsylvania" as the guest of her builders, the Cramps, of Philadelphia, to witness the government speed trial on the well-known Cape Ann course off the coast of Massachusetts. Outside of the small party of invited guests and the ship's trial crew of 450 officers and men, the persons on the ship most immediately interested in the trial were the Government Trial Board, composed of eminent officers of the navy, and the officers and representatives of the company that built the ship. To the first named, a speed trial is an event of profound importance, since upon it depends the acceptance by the government of the United States of a vast and complicated machine which, in the completed condition, will represent the expenditure of between five and six million dollars from the national treasury. To the representatives of the firm, the issue is of even more vital importance, since it involves the payment to them of a sum of nearly four million dollars, and what is of even more importance, the prestige of the firm is greatly at stake; for of all misfortunes that may happen to a big shipbuilding firm, there is none that can give more positive chagrin than to know that such and such a great warship constructed by themselves, and designed for 20 or 22 knots an hour, must go down on the official register as having done no better than 19 plus or 21 plus, as the case may be. On the other hand, it is always an object of laudable ambition and keen competition among the respective builders of a class of sister ships to be able, as in the case of the "Pennsylvania," to say that she heads her class in speed and economy of coal consumption.

The performance of the "Pennsylvania" in exceeding the contract speed by 0.43 of a knot, and the contract horse-power by 5,000, is a result that is gratifying both to the government and to the builder. It has always been the policy and tradition of our Bureaus of Construction and Engineering to encourage the hearty co-operation of the leading shipbuilding firms of the country; and in this particular case, the excellent results are directly attributable to certain modifications in the boiler room and engine room, which, as the trials have shown, resulted in greatly improving the speed and efficiency of the ship. The contract for the six vessels of the "Pennsylvania" class called for the development of a speed of 22 knots an hour, with an indicated horse-power of 23,000. The builders of the "Pennsylvania" decided that, by using a different type of water-tube boiler, and making certain modifications in the triple-expansion engines, they could secure a larger indicated horse-power, and thus serve the double purpose of safeguarding their own interests and giving the United States government a better ship. The suggested changes which were allowed by the government were as follows: The battery of thirty Babcock & Wilcox boilers was replaced by a battery of thirty-two modified Niclausse boilers, the modifications being in the direction of larger tubes and drum, and a general simplification of details. The main steam pipe was increased from 13 inches to 15 inches diameter, because it was considered that for a piston speed of nearly 1,100 feet a minute, a pipe of the larger diameter would be a necessity. The boiler pressure was raised from 265 pounds to 300 pounds, and the arrangement of the cylinders was modified, so as to give a more direct flow to the steam; the order in the departmental design being low pressure, high pressure, intermediate, and low pressure, which was changed in the Cramps' design to high pressure, intermediate, low pressure and low pressure. Another radical change was that, instead of the low-pressure cylinders being assisted by introducing live steam from the boilers, this connection was dispensed with, and, instead, the exhaust from the auxiliaries was fed direct to the low-pressure cylinders. It will thus be seen that the changes were thoroughly in touch with the latest marine practice, involving high boiler pressure, ample steam-pipe connections to convey an abundance of steam to the cylinders, and a literal adherence to the principles of triple-compound expansion, by using live steam only in the high-pressure cylinders, and allowing it to develop its full expansive efficiency from throttle to condenser.

The value of these changes is seen in a comparison of the trials of the "West Virginia" with those of the "Pennsylvania," the first-named ship being built strictly to the original designs. On her trial trip the average speed of the "West Virginia" was 22.12 knots with 25,750 horse-power, on a coal consumption of 3.2 pounds per indicated horse-power per hour. The "Pennsylvania" averaged 22.43 knots with an average indication of 27,750 horse-power, on an average coal consumption of 2.2 pounds per horse-power per hour, the temperature in the uptake in the first case being over 1,000 degrees, and in the case of the "Pennsylvania" 650 degrees. We quote these figures not only for their intrinsic interest, but as showing the wisdom of the departmental policy of encouraging the private builders to offer and put in practice their own amendments to departmental designs. The low coal consumption is, perhaps, an even more valuable feature than the higher speed, for it means that if the "West Virginia" and the "Pennsylvania" were both using

their forced draft in chase of a fast cruiser of the enemy, the "Pennsylvania" would be able to follow the chase for 50 per cent longer time than her consort. In other words, by virtue of her higher economy, her radius of action, on the same amount of coal, when using forced draft, is just 50 per cent greater than that of the sister ship.

In the popular mind, the speed trials of a United States warship are associated with much that is spectacular, both in the event and in the preparations for it. Although the editor boarded the ship at the New York navy yard, under the impression that the reality would prove considerably less lurid than its oft-repeated descriptions might lead the layman to expect, he was not altogether prepared to find such a cool, matter-of-fact, everyday air prevailing both above decks and below. There were no chunks of unburned coal, "big as a man's fist," being thrown crater-like from the "belching" smokestacks, nor were there any exhausted firemen brought up and laid on deck to be revived before plunging again into that "inferno" below. Everything was orderly, methodical, and highly scientific. The trial was simply the accomplishment of results that had been carefully planned and confidently predicted months and years before they happened. Indeed, just as the vessel swept over the line at the start, her builder predicted her speed to the writer, with an accuracy which proved, when the trial was over, to be only one-tenth of a knot too low.

The Cape Ann course is selected mainly because it affords deep water—an important element in obtaining estimated speeds—and because the course is sufficiently near to the shore to admit of the buoys by which it is marked off being accurately located by triangulation from the shore. The total length of 44 knots is divided into seven approximately equal lengths of about 6 knots each. Near each buoy, and on the landward side of it, is anchored a United States warship, which does the double duty of affording a large, conspicuous object to assist the captain of the vessel on trial in steering a true course, and also affording a means of gaging the speed of the tide at each particular mark at the time when the ship passes. The vessel runs the full length of the course, then makes a wide turn, and steams back over the same course. In estimating her average speed over each leg of the course, the speeds of the tide at the two buoys are taken, and their mean is added or deducted, according as the tide is adverse or favorable, to the speed of the vessel over that leg. The average of the fourteen speeds thus arrived at gives the average speed of the ship for the whole 88 knots.

In a case where deductions at the rate of $25,000 for every quarter of a knot that the vessel falls below contract speed, are involved, great accuracy is necessary. The time is taken by means of two vertical sighting rods placed transversely to the axis of the ship on the upper, forward bridge. At the instant that the particular buoy is in line with these two sights, the timing officer calls out "Mark," and the time is accurately taken with a chronometer. It is not generally understood how greatly the speed of the ship depends upon the steersman; for if she veers ever so little from her course, it means not only that she travels a proportionately greater distance, but that the retarding effect of the helm in bringing her back to her course pulls down the speed very materially.

Upon entering the engine room, the conditions did not strike the writer as varying greatly from those that obtained when he made a chance visit to the engine room of the "Deutschland," during a passage across the Atlantic. Each engineer and oiler was at his particular post and, of course, was closely attentive to his duties. Perhaps the only difference that one could note was the large amount of saponified lubricating oil (looking for all the world like soapsuds) that was spattered over the moving parts, frames, and bed plate. This was inevitable in a case like the present, where the engines, although they were fresh from the builders' yard, were being pushed to their maximum power. Passing through the airlock that leads into the boiler rooms, one was struck with the same quiet orderliness and utter absence of excitement or nervous tension. The coal was being brought by a couple of men from the bunker door at the end of the foot plate, a sack at a time, and emptied into a long heap athwartships, and midway between the twelve fire doors of the four boilers in the compartment. The fire doors were numbered in pairs, the doors having the same number being on opposite boilers and diagonal to each other. At one end of the foot plate stood a group of firemen, with a boy in their midst who was holding a watch. At two-minute intervals he would call out a number, and instantly two firemen would come out upon the floor plate, coal the fires corresponding to the numbers called, throwing on a half dozen shovelfuls, and then step back to join the quiet little group at the end of the floor plate. This method was followed in all the compartments, and it meant that each furnace received a thin layer of coal once in every twelve minutes. Previous experience had shown that this rate of firing would provide the thin, evenly-spread bed of coal necessary to maintain a full head of steam at 300 pounds boiler pressure.

With a view to determining the actual coal consumption, the coal, before the trial, was sacked and weighed; and many of our readers will be astonished to learn that the coal used was the straight run of the mine, and cost only $2.75 a ton—thus disposing of another of the little fictions that have grown up around warship speed trials, to the effect that the coal was picked by hand and cost something over $10 per ton.

Our observations of the whole trial confirm the statement that there is no reason why such a ship as the "Pennsylvania," after being turned over to the navy, should not for years to come, repeat, or even exceed, her trial performance. It is true the trial crew was a special one, well trained to its work; but the navy is also paying special attention to its fire-room staff, and it has some very efficient crews in the service. Moreover, the engines on this trial were perfectly new, and no doubt after several months of service they will limber up and show as good, or better results.

THE HEAVENS IN DECEMBER.

BY PROF. W. M. REED.

On December 31, at midnight, the earth is at perihelion, and therefore nearest to the sun of any time during the year. But how far we are at this time from our source of heat is still doubtful by perhaps 100,000 miles. Since B. C. 270 many attempts have been made to determine this most important of all distances in the solar system. By other means the relative distances of all the heavenly bodies can be found. But to ascertain the dimensions of the solar system in miles, we must know the distance from the earth to the sun. Mr. Arthur R. Hinks has just made a discussion in the Monthly Notices of the Royal Astronomical Society, of the parallax of the sun, as deduced from photographs of Eros, taken during the last opposition of November 7 to 15, 1900; 295 plates were exposed at observatories in the following places: Algiers, Lick Observatory, Cal., Northfield, Minn., Tacubaya, Mexico, Cambridge, Minneapolis, Oxford, and Paris.

The measurement of these plates gives a value of the parallax of 8.7966 sec. ± 0.0047 sec., which corresponds to a distance of about 92,861,000 miles ± 50,000 miles, which places the sun about 36,000 miles further away than it was formerly supposed to be. Aristarchus in B. C. 270 obtained a parallax of 180 sec. by observations on the moon when its elongation was 90 deg. from the sun, or one-half phase. In 136 A. D. Ptolemy, from observations on the earth's shadow, made the parallax 170 sec. The Hindoos about 1100 A. D. got 240 sec. Corpernicus in 1543, also from observations of the earth's shadow, got 240 sec. Kepler, from the diurnal parallax of Mars, obtained 60 sec. in 1620. By the same kind of observations, Flamsteed, in 1672, reduced the parallax to 10 sec. Since 1850 over fifty determinations of the solar parallax have been made. They all lie between 8 sec. and 9 sec. Until quite recently the accepted parallax was 8.80 sec.

On December 20 Aldebaran is occulted by the moon. As seen from Washington, the star disappears behind the moon at 8h. 25m. Eastern standard time, and reappears at 9h. 46m. But on account of the parallax of the moon, this time must be considerably altered to suit conditions at other places. On December 2 Mars is also occulted. The Washington time of disappearance is 2h. 15m. A. M. Eastern standard time, and 3h. 16m. A. M. for reappearance.

The disappearance of a bright star behind the moon is an extremely interesting phenomenon to watch. It gives many people their first impression of how rapidly the moon is moving among the stars. Then the very sudden extinction of the star is an impressive sight. At first the moon will appear to gain rapidly on Aldebaran. Finally this speck of light will seem to be fastened to the edge of the moon, and to stay in this position longer than the observer expects. But suddenly the star will be gone. Its reappearance from the other side will be equally startling. This phenomenon is one of our strongest arguments that the moon has either no atmosphere or an extremely trifling one. Even in a small telescope it is obvious that there can be no very great gaseous envelop to our satellite. For the mountains are just as distinctly seen at the edge of the disk as they are at the center. In 1792 Schröter thought he perceived a twilight band on the moon, and argued from that, that the moon must have an atmosphere about one-thirtieth as dense as ours. But such an atmosphere should so bend the light of occulted stars as to make the time from disappearance to reappearance much less than we should expect from the measured diameter of the moon. Sir George Airy found only 4 sec. for the difference in the diameter of the moon as deduced from direct measurement and from occultations of stars. Also from this 4 sec. must be subtracted the effect of irradiation, which is far from a negligible quantity. From these observations he concluded that the moon's atmosphere, if it has any, must be at least two thousand times less dense than our own at sea level. Furthermore, as the star approaches the lunar disk, certain rays of its light should first be absorbed by the lunar atmosphere. Such an example of selective absorption is noticed on every clear day when the sun sets. The absorption in this case is so great, on account of the greater mass of air through which the sunlight must travel, that its color is perceptibly changed. To test this effect of a possible lunar atmosphere, Sir William Huggins watched the spectrum of the star Epsilon Piscium during occultation, but found that the whole spectrum disappeared as quickly as the star itself. Prof. Comstock has recently come to the conclusion from occultation of stars that the lunar atmosphere cannot have a density exceeding one five-thousandth that of the earth's. Prof. W. H. Pickering took photographs of Jupiter during an occultation in 1892. He concluded that the disk was slightly flattened as it approached the moon's limb, on account of the effect of the lunar atmosphere. These measurements gave a maximum density of the refracting medium of one four-thousandth of our atmosphere. It is interesting that during this month both kinds of occultations can be observed.

On December 16, at midnight, Jupiter is in conjunction with the moon. The sun is at the winter solstice, which marks the beginning of winter, on December 22 at 1 A. M.

On December 20 at 6 P. M. Venus is in the southwest at an altitude of 15 deg. The planet will continue to grow more brilliant throughout the month. At the same time Saturn will be in the same quarter of the heavens at an altitude of 22 deg. At 6 A. M. Mars will be seen in the S. S. E. at an altitude of 40 deg. It will be a short distance above the bright star Spica, in the constellation of Virgo.

During the evening Jupiter will be a very prominent object. At about 8 P. M. it will be in the direction S. S. W. at an altitude of 57 deg. It will be easily distinguished by its great brilliancy.

Mercury is at greatest elongation on December 13, when it is 20 deg. from the sun. It will then be close to the horizon just after sunset. But at this season of the year the ecliptic makes such an acute angle with the horizon at sunset that it is very difficult to see Mercury unless the weather is exceptionally clear.

At 8 P. M. on December 20, Orion is S. S. E. at an altitude of about 30 deg. The three stars that form the belt are almost vertical to the horizon.

Farther to the north, in a direction about E. N. E., are the Twins—Castor and Pollux. They will be about the same distance above the horizon as Orion's Belt. A line connecting these two stars is also nearly vertical to the horizon. Directly above Orion's Belt is the red star Aldebaran, and around it the group of faint stars known as the Hyades. Still further toward the zenith, 65 deg. from the horizon, is the famous group of the Pleiades, consisting of six stars easily seen and six others that are seen with difficulty. Below Orion's Belt and close to the horizon is the dog star Sirius—the brightest of the fixed stars.

Princeton University Observatory.

SCIENCE NOTES.

Only 14,995,272 acres, or 15.7 per cent of the whole area of Japan, exclusive of Formosa, consists of arable land, and 55 per cent of the agricultural families cultivate less than two acres each; 30 per cent cultivate 2 acres or more up to 1½ cho, or a little less than 3¾ acres, leaving 15 per cent of the farmers who cultivate the farms of 3¾ acres or more.

An important and valuable discovery relative to the deadly sleeping sickness has been made by the Liverpool School of Tropical Medicine. The cause of this disease, according to the results of elaborate diagnoses that have been made, is attributable to "trypanosomiasis," i. e., the presence in the blood, and in the fluids of the brain and spinal cord, of some form of the microscopic parasite known as "trypanosoma," which is propagated by the tsetse fly in South Africa. From the close observations that have been made upon the afflicted patients, the symptoms and the danger bear some relation to the greater or less abundance of the parasites, and develop seriously when they have entered the cerebro-spinal fluid. The parasites may be present in the blood of deeply-seated organs, when they are not to be found in that which is drawn from a skin puncture, and their frequent temporary disappearances from this surface blood renders it difficult sometimes to be certain of their presence in the system. The expedition organized by the school also discovered a blood-sucking larva, which thrives in many parts of the Congo. During the daytime this larva conceals itself in the cracks of the native floors, and only attacks its victims during the night. When dug up they are found to be full of bright red blood, thereby testifying to the severity of their attack during the previous night. It is the larva of the Glossina fly which is apparently harmless in the imago state. This discovery is of great value, and systematic measures to combat its injurious nature will at once be inaugurated.

A LOCOMOTIVE IN SERVICE SIXTY YEARS.

BY HERBERT T. WALKER.

In the earlier days of railroads, the life of a locomotive engine was longer than it is now, for even within the last decade many engines built under the personal supervision of Stephenson, Bury, Baldwin, and Rogers were in active service on the railroads of the United States and Great Britain, as well as on those of other countries that depended on us and the British locomotive builders for their supply of railway motive power.

During say the first forty years of railroad history, the engines were not, as a rule, worked to their fullest capacity; but as time went on, the requirements of railroad work became more exacting, and the period during which an engine was in the roundhouse grew gradually shorter, until to-day a locomotive, especially if it is in freight service, is almost constantly at work, the only intervals being the time necessary for oiling, inspection, and repairs.

As a consequence of these present conditions, one seldom sees a really old locomotive in service; but a notable exception is illustrated in the accompanying engraving, showing an engine which has been in constant use for nearly sixty years on a branch railroad in Santiago de Cuba.

This locomotive was built by M. W. Baldwin, and, by the courtesy of Messrs. Burnham, Williams & Co., who have, at the writer's request, referred to their old records, we are able to publish some interesting details of a design of engine originated by one of the most celebrated of the pioneer locomotive builders of the United States.

It appears that in the years 1847 and 1848 two locomotives of the type illustrated were built for the Havana & Guines Railroad, and one of them is doubtless the engine forming the subject of this notice. The cylinders were inside-connected and were 14½ inches diameter by 18 inches stroke. The engines weighed somewhere about 18 tons.

The leading feature of this design is in the wheel arrangement. All the wheels are drivers, and from the engraving it would appear that the engine is without a truck; but in reality the four front wheels have inside journals running in boxes held by two deep wrought-iron beams, one on each side. These beams are unconnected and entirely independent of each other, and their pedestals are bored out cylindrically to receive cylindrical journal boxes. The main engine frame on each side is directly over each beam, and a spherical pin, running down from the frame, bears in a socket in the beam midway between the two axles. Each beam can thus independently turn, horizontally or vertically, under the spherical pin, and the cylindrical boxes can also turn in the pedestals, so that in passing over a curve, the front pair of wheels can move laterally in one direction—say to the right—while the next pair moves in the opposite direction, or to the left, the two axles always remaining parallel to each other and to the two rear axles, which latter are mounted rigidly in the main frames, as in ordinary locomotives.

The operation of these beams is therefore like that of a parallel ruler, and the spherical pins allowing them to move in a vertical as well as a horizontal plane, they act as equalizers, and so permit the four wheels to accommodate themselves to a rough, uneven track.

It should be explained that the coupling rods are made with ball and socket joints, to enable them to conform to the lateral movements of the wheels. This invention of Baldwin's was known as the "flexible beam truck," for which he secured a patent August 25, 1842; it solved the problem of producing a locomotive with a flexible wheel base, in which the total weight of the engine was available for adhesive purposes.

Other details of this engine may also be noted. It will be observed that the valve chest has two valve stems. The explanation of this is that the chest has two compartments, with a separate slide valve in each chamber. One valve cuts the steam off at full stroke, and the other at an intermediate portion thereof. By suitable levers these valves can be worked either separately or together. This device was one of many invented by Baldwin to take the place of the Stephenson link motion, which he did not consider to be a satisfactory valve gear.

The large smokestack indicates that this locomotive is a wood burner, which fuel requires special provision for preventing an excessive discharge of sparks from the chimney when the engine is under way. Even with the most approved stacks, wood-burning engines throw much fire, and many of us can recall an early day, when we watched the night express as it speeded by, sending showers of bright sparks flying over the dark landscape.



ONE OF THE OLDEST LOCOMOTIVES IN USE.

It has been running on a Cuban branch railroad out of Santiago for over sixty years.

A TILTING LOCK-CHAMBER.

A peculiar form of canal-lock, indeed perhaps more peculiar than serviceable, has been invented by Charles A. Cardot, of Paris, who hopes by means of this device to raise or lower a ship of any size from the upper level to the lower, or *vice versa*, without losing a drop of water.

The invention, as the two accompanying illustrations clearly show, comprises essentially a lock-chamber, *C*, permanently in communication with the water, *D*, of the lower level. It will be observed that the bottom of this chamber is formed with two inclines of unequal length, so that the highest point will lie nearer the upper level, *E*, to permit the raising and lowering of the vessel. At this highest point a ridge, as it were, is formed, which constitutes the fulcrum for a floating-chamber mounted to rock on the shaft, *B*.

This floating-chamber is constructed with double walls, constituting an air-chamber, and comprises in itself a water-compartment, the ends of which are closed by gates *G* and *H*. At the bottom of the air-chamber a track is laid, on which a weight, *M*, is mounted to travel. The weight, *M*, is connected, by means of a cable passing over a pulley, with a float, *L*.

In order to tilt the floating chamber down to the lower level, the weight, *M*, is caused to travel in the direction of the lower level, whereupon the corresponding end of the floating chamber descends. When the lower level has been reached, the gates, *H*, are opened, and the vessel continues on its journey. In order to raise a vessel from the lower to the upper level, it is obvious that the reverse operation must be gone through.



The Lock-Chamber Tilted Down to the Lower Level.



The Lock-Chamber Rocked to the Upper Level.

A TILTING LOCK-CHAMBER.

New Bread-Making Process.

United States Consul Mahin, at Nottingham, England, says in a recent report:

"A journalist, Mr. W. Pickering, whose address is not given, though it is presumably London, is credited in a current newspaper item with an invention which entirely dispenses with the customary night work in bread making. The preparation of the dough takes most of the time required in the ordinary baking process, as, after mixing and kneading, it must be left to rise, which requires from four to twelve hours. Mr. Pickering's invention reduces this time to about one hour. No additional plant is required and no extra ingredient is put into the bread. 'The effect is produced by the action of temperatures,' explains the descriptive article.

"At a practical demonstration recently given, it is said that the flour was made up into dough ready for the oven in fifty-nine minutes, and the batch of twenty-five loaves was produced from the raw flour in two hours and thirty-five minutes. The flour was weighed and the number of loaves compared with the number produced by the ordinary process, and it was found that eight more quartern loaves than usual are produced from a sack of flour."

Cement production in the United States in 1903 amounted to 28,454,140 barrels, according to the United States Geological Survey. Of this amount 20,897,973 barrels were Portland cement, 7,030,271 barrels were natural cement, and 525,896 barrels were slag cement. The amount made in 1903 was about 2,700,000 barrels more than in 1902, the output in the preceding year.

NEW FORM OF LIQUID RHEOSTAT FOR STARTING ELECTRIC MOTORS.

BY OUR BELGIAN CORRESPONDENT.

When circuits into which artificial resistances are introduced are traversed by heavy currents, coarse resistance wires, straight or coiled, and stretched upon insulators in the open air, ordinarily are employed. But it is possible, also, to use a solution of a metallic salt in which are immersed plates of the same metal as that of the dissolved salt. The resistance of the bath is modified at will by varying the distance apart of the plates. When it is unnecessary to pay any attention to the electromotive force of polarization, wrought iron electrodes and a solution of carbonate of soda are employed.

The use of liquid resistances offers certain advantages. The superheating that not only damages metallic resistances, but, under certain circumstances, constitutes a danger, cannot occur when liquid resistances are employed. Moreover, the putting of metallic resistances out of circuit, which is usually effected by a switch moving over a series of contacts, destroys the contacts and necessitates expensive repairs. Liquid resistances are, therefore, superior to the others, and they would certainly have been more widely used were it not for certain disadvantages inherent in them. These may be summed up as follows: (1) the creeping of the salts of the liquid, and, consequently, a diminution in the insulation of the apparatus; (2) evaporation, which ruins the terminals, the contacts, and the conductors of the resistance box; (3) the adherence of the oil and air valves; (4) the absence of "overload" and "no voltage" releases (maximum and minimum).

A new rheostat, designed to remedy these inconveniences, has been invented by Mr. Woolliscroft and has been put on the market by the Sandycroft Foundry Co., Limited, of Chester, England. It consists of a cast-iron drum, hermetically closed and filled half full of a solution of soda and water. The drum is provided externally with contacts and terminals, and internally with electrodes. In Fig. 1, on the left, is shown the friction contact segment insulated from the drum, and just beneath the "no resistance" contact, or the one with which the resistance is all cut out. The distance that separates them is such that it can be completely bridged by the forked current collector, which is seen mounted on top of one of the supporting posts of the drum.

The drum is mounted on two of these insulated posts, and has on its side a hole for filling it with liquid. The hole is closed by a screw plug containing a small hole that acts as a safety valve and gives vent to the gases engendered by electrolysis. Since this aperture is never submerged, no losses of liquid can occur.

A minimum release magnet (see Fig. 1 on the right), connected with the shunt winding of the motor, is mounted, together with a handle, on a lever that revolves upon the same axis as the drum. When this magnet is energized, if the handle is placed in a horizontal position, a catch on the armature of the magnet engages with another on the side of the drum. Then, as the handle is raised, the drum, being locked to it, moves along with it. The effect of this movement is to plunge the two electrodes attached to the drum into the liquid. The more they are submerged, the less the resistance in the circuit becomes, until the drum finally reaches the end of its travel, and the resistance is all cut out by means of the special contact already mentioned.



Fig. 1.—New Type of Electric-Motor-Starting Rheostat with Automatic "No Voltage" and Overload Releases.



Fig. 2.—Reversing Switch for 5-Horse-power Electric Motor.



Fig. 3.—Diagram Showing Circuits of "No Voltage" and Overload Release Magnets.

LIQUID RHEOSTAT FOR STARTING ELECTRIC MOTORS.

A "maximum" release magnet is contained in one of the cast-iron supports. This release magnet, in case the current that is passing should be excessive during the operation of starting or during the running, short-circuits the minimum release magnet, causing it to let go the drum, which immediately returns, by gravity, since it is suitably weighted, to the position of interruption.

The diagram, Fig. 3, shows the electrical connections clearly. The current, entering from the mains, passes through the heavy wire of the overload magnet in the supporting post of the drum, and then in through the axis to one resistance plate of the drum. The other resistance plate is connected with the insulated segment on the outside, and the current passes from this segment through the collecting forked contact and back to the mains, thus completing the circuit. The connections of the "no voltage," or underload, magnet are indicated in lighter lines, running from the shunt coil around the magnet and back to the wire in the axis of the drum, which connects with the other side of the armature and shunt coil, as above stated. When an overload occurs, the armature of the large magnet rises, and the plunger on its upper end completes the circuit through the two points shown, which, being a path of less resistance for the current, is taken by the latter in preference to that through the magnet, thus causing the latter to release its armature.

The same company is also constructing a special type of reversing switch based upon the same principle. Fig. 2 shows one for 5 horse-power. It is particularly adapted for elevators, cranes, etc., in which motors requiring a reversal of the current are employed. The house also adapts the system to use with polyphase currents, for which it is particularly well fitted.

The advantages claimed for the system are the following: Simplicity of construction, absolute efficiency in its operation, and absence of sparks. The motor cannot be set in operation too rapidly and may be stopped either through a bipolar apparatus or a liquid resistance. There is no limit of maximum time for the starting, and it is impossible for the resistance to burn. A motor may be stopped at any moment by pressing a button. The apparatus requires scarcely any attention. By varying the density of the solution, the resistances may be adapted to voltages of as high as 700. The apparatus can be easily carried without loss of liquid, and is always ready for operation.

The reduction of fire risks makes these apparatus recommendable for mines, flour mills, powder mills, oil manufactories, and, in general, for all industrial exploitations in which risks are run from the presence of inflammable materials, dust, or gas.

These resistances, moreover, have already been widely sold and, in every case, have given entire satisfaction. In many cases in which metallic resistances had not proved a success, as a consequence of the difficult conditions in which they had to operate, this system has surmounted all difficulties.—Translated for the SCIENTIFIC AMERICAN.

Transporting Meteorographic Apparatus up the Slopes of the Portitjokko.

THE REGISTRATION OF METEOROLOGICAL PHENOMENA IN LAPLAND.

BY EMILE GUARINI.

M. Axel Hamberg, instructor at the University of Stockholm, has for the last two



The Meteorographic Station upon the "Sahkok" at an Altitude of 8,500 Feet.



The Meteorographic Station upon the Portitjokko from the Southwest.

THE REGISTRATION OF METEOROLOGICAL PHENOMENA IN LAPLAND.

years been engaged in establishing upon the Alps of Swedish Lapland an automatic meteorological observatory something like the one installed with so little success upon the summit of Mont Blanc by M. Janssen of the Institute of France.

Up to the present, two stations have been established, one upon Sähkok Mountain at about 3,500 feet above the level of the sea, and the other upon the Portitjokko at an altitude of 6,560 feet.

The first apparatus stopped for the first time after running for a month, and had to be taken to Stockholm for reconstruction. Each apparatus is calculated for an uninterrupted operation of one year, and weighs about 2,200 pounds. In order to facilitate carriage, the instruments are constructed in parts that can be transported by reindeer. The weights of the clockwork movement weigh 660 pounds, and are divided into parts, each weighing 35 pounds.

The second experiment gave good results. The registration is obtained by means of a bar, which, three times an hour, falls across needles and produces in the paper perforations corresponding to each of them. The great difficulty to be surmounted is the hoar frost. The Portitjokko station, for example, was, after a few months, completely surrounded by a stratum of frost of at least three feet in thickness, and the apparatus very naturally ceased to operate. The instruments were then taken down to 500 feet from the summit, but, even at this altitude, the formation of frost interfered with their operation, especially in autumn. It is then almost impossible to prevent interruptions in the registration of the velocity and direction of the wind. In order to obviate this inconvenience, M. Hamberg has the summit apparatus cleaned from time to time by a Laplander, and after this the running proceeds uninterruptedly till the succeeding autumn.

Not only the frost, but the fine snow, also, which it is very difficult to exclude, causes serious trouble. On the other hand, in order to assure the proper operation of the apparatus, the air that surrounds them in the hut must be kept as dry as possible, else the paper will wrinkle and the pieces of iron will rust, and, at every variation of temperature, the frost will deposit upon the clockwork movement and stop it.

In order to dry the air to as great a degree as possible, it became necessary to place paper cylinders around the clockwork movement, and, around the registering apparatus, an iron plate casing containing cups filled with chloride of calcium. It was owing only to such precautions that the running of the apparatus became uniform during the entire winter. The apparatus installed at 3,500 feet altitude has operated almost continuously for two summers, and the second, placed at 6,000, has operated equally as well. The anemometer and the weather vane, however, have sometimes been stopped by the autumnal frost.

The winding up of the clockwork and the changing of the paper bands of the registering apparatus are effected but once a year. The registration during the year requires the use of 65 feet of paper. The weight that actuates the clockwork movement descends but 60 inches a year. This movement was constructed by M. G. W. Linderoth, a Swedish horologist.

A complete station comprises two huts, one containing the paper-cylinders, the clockwork, and the registering apparatus, and the other the rain and snow registering apparatus. This latter is suspended from spiral springs in a large cask. When there is a fall of rain or snow, the cask descends according to the greater or less quantity of material that it receives, and thus causes the registration. The huts are constructed of wood and iron plate.

The problem of the meteorography of high altitudes is therefore solved, or at least will be ere long. From now on the curves obtained will probably teach us much upon this subject, for it is to be anticipated that M. Hamberg's experiment will not remain isolated, and that analogous observatories will be installed at numerous points of the globe. Perhaps it will even be possible to resume M. Janssen's experiment upon Mont Blanc.

Death of Gen. Di Cesnola.

Gen. Luigi Palma di Cesnola, soldier, archæologist, director of the Metropolitan Museum of Art, died November 22, 1904. General di Cesnola's career was picturesque. Born in 1832, in Piedmont, Italy, he entered the army at the age of seventeen, served through the Italian war against Austria, and was decorated on the field of battle for bravery. Later he went through the entire Crimean war and was present at the fall of Sebastopol. His fighting career did not end there. He came to this country in 1860, taught languages for a while, and entered the United States service as an instructor in tactics and cavalry drill. When the civil war broke out he raised a company and fought in many important battles. He was captured by the Confederates and spent nine months in Libby Prison. At the close of the war President Lincoln promised him a promotion to the grade of brigadier-general. Although the President's untimely death prevented him from carrying out this promise, Di Cesnola always was known as a general.

It was as consul to Larnica, Cyprus, to which post he had been appointed by Lincoln, that Gen. Di Cesnola began his famous archæological investigations. For twelve years he thoroughly explored Cyprus, made excavations in which he gathered thousands of relics, which he afterward catalogued and described in his book "Cyprus: Its Ancient Cities, Tombs and Temples." This Cyprus collection may be regarded as the nucleus of the present Metropolitan Museum of Art. Gen. Di Cesnola became a trustee of the museum in 1877 and was later made its director. The museum as we know it to-day may be regarded as a monument to his energy, enterprise, and rare executive skill. In his death the museum has lost a director whose place it will be very difficult to fill.

AN INTERESTING RELIC.

In the splendid cathedral church of Rouen is a suite of three or four rooms containing what is known as the "Trèsor." This is a collection of very valuable and interesting relics, forming quite a little museum, to which admission may be obtained for the modest fee of 25 centimes. To an Anglo-Saxon quite the most interesting article in the collection is the plain leaden casket in which was buried the heart of the famous King Richard Cœur-de-Lion, who, it will be remembered, was slain by a bolt from the crossbow of Bertrand de Gourdon at the siege of the castle of Chaluz. His body was buried at the feet of his father at Fontrevault near Tours, but his heart was incased in two leaden caskets and buried in the cathedral of Rouen, "the faithful city."

The exact place of its burial seems to have been forgotten, but it was re-discovered in 1840, placed in a new receptacle, and reburied in the choir. The old leaden cases, the outer one of which was in a most dilapidated



THE CASKET THAT CONTAINED THE HEART OF RICHARD COEUR-DE-LION.

condition, were placed in the "Trèsor," with the following inscription:

CERCUEIL
ET
BOITE DE PLOMB
OU FÛT RENFERMÉ
LORS DE SA SEPULTURE EN 1199
LA CŒUR DE
RICHARD CŒUR-DE-LION.
TROUVÉS EN 1840
DANS LE SANCTUAIRE DE LA CATHEDRAL
DE ROUEN.

The inner case is in comparatively good condition, the inscription being perfectly legible after all these hundreds of years. The Latin is somewhat peculiar, and it is curious to find that at a period when the art of working in metals was at an advanced stage, the engraver of the inscription on the coffer which was to contain the heart of such a high and mighty potentate did not take the trouble to ascertain what space he required for the king's name, so that he had to carry over the terminal letter to the next line. It is noteworthy, too, that Richard is styled "Regis Anglorum," "King of the English"—not of "England"—while no reference at all is made to Normandy or Aquitaine. The box is about a foot long, eight inches wide, and five deep.

The Current Supplement.

The current SUPPLEMENT, No. 1509, opens with an excellently illustrated article by the St. Louis correspondent of the SCIENTIFIC AMERICAN, in which some interesting models at the Fair are described. One of the finest of these shows the methods of anthracite coal mining as carried out in the State of Pennsylvania. Another represents naval warfare on a mimic scale. Mr. A. A. Campbell Swinton recently read before the British Association an instructive paper on the development of electricity from water power. The paper is published in the current SUPPLEMENT. The SUPPLEMENT will hereafter publish every two weeks an article by Prof. N. Monroe Hopkins on experimental electro-chemistry. When completed the series will constitute a splendid student's manual. The articles are noteworthy for their practical character, the many clear drawings of easily-constructed apparatus that are used as illustrations, and the intelligible exposition of the subject. "A Chemist in the Days of the Stuarts" is the title of a contribution in which much curious historical information is given. The Navy Department exhibit in the Government Building at St. Louis is fully described and illustrated. The same applies to the exhibit of rolled and flanged steel plate. Douglas W. Freshfield's paper on "Mountains and Mankind" is concluded.

Electrical Notes.

The British Admiralty has obtained the exclusive use of a new apparatus, which is to be employed in connection with wireless telegraphy. Precisely what the invention comprises is not known, as it is a jealously-guarded secret. It is called a cryptogram, and is the invention of a Swiss mechanic. Its purpose is to prevent the interception of wireless messages, except by a person or station provided with the same device. The apparatus is stated by the English naval authorities to be perfect in operation, since when five of these instruments were submitted by them to a series of exacting tests, they proved so successful that the device was procured by them outright.

Mr. L. R. Lee, of the electricity station of the Manchester, England, corporation, has invented an apparatus for the ventilation of watertight-incased transformers used in underground stations, which are liable to flooding. In this invention discriminating valves are fixed to the case or tank containing the transformer, thereby enabling a continual supply of air to enter and leave the tank. One advantage of this device is that any water that may be left in the transformers during the process of manufacture can make its escape, by condensation on the underside of the cover, and then running out of the inclosing tank, the cover being formed in such a way that the water cannot remain inside. No apprehension need be entertained regarding the safety of a tank fitted with these valves in the event of flooding, for even if the water rises completely over the transformer, none can enter the case, and as soon as the water is drained away or removed, ventilation is at once automatically resumed.

A new method of wireless telephony is being developed by Prof. Quirino Majorana, of Rome. This system, according to reports in the Italian technical press, seems to be based essentially on the Marconi wireless telegraphy. In the latter, as is well known, a series of shocks corresponding to the various sparks is produced at the receiver, when the sparks are made to jump at the transmitting station. The receiver designed by Marconi enables the operator to decipher the telegrams acoustically, listening to the series of sparks. The number of sparks, however, does not exceed 10 per second in the Marconi apparatus, whereas Majorana has increased this number up to 10,000 per second, though the various sparks are evidently weaker than those used in wireless telegraphy. Persons placed at the receiving station will, therefore, not note anything, the succession of sparks being too rapid and the sparks themselves too similar to one another. As soon, however, as the uniformity of these sparks is interrupted artificially by the oscillations of the human voice, every word will be transmitted truly to the receiver. The Cologne Gazette, in a recent issue, points out the similarity of Majorana's endeavors to the scheme outlined by Prof. H. Th. Simon and Dr. Reich. According to the researches of these experimenters, the problem of wireless telephony by means of Hertzian waves has been solved at least theoretically. Transmitters so far used in wireless telegraphy yield trains of waves interrupted by relatively long pauses, and corresponding to the various spark discharges. Though the interval between the passage of a group of waves and the production of the subsequent group is only a minimal fraction of a second, this short interruption in the series of oscillations will be quite sufficient to render any transmission of acoustic waves of the human voice to a distance impossible. Wireless telephony requires continuous wave currents. These are obtained by Prof. Simon by the aid of an Arons-Hewitt mercury lamp as vacuum spark gap, when the discharge potential between the spark electrode exceeded 50,000 volts, and the frequency of the spark discharge 10,000,000 per second, that is much more than according to Majorana. In wireless telephony the intensity of the spark wave will have to be adapted to that of the acoustic waves. This will be possible either by the wave lengths or by the intensity being altered. The first scheme has been chosen by Prof. Fessenden, whereas Majorana seems to have adopted the second alternative.

Correspondence.

German Bells at St. Louis.

To the Editor of the SCIENTIFIC AMERICAN:

I was much interested in your description and illustrations of the German national pavilion at the St. Louis Exposition, especially in your reference to the bells. You are in error, however, in saying they were purchased by an eastern city, as they were purchased for St. John's German Lutheran Church, of Reading, Pa., the Rev. Dr. J. J. Kuendig, pastor. F. S. WERTZ.

Reading, Pa., November 18, 1904.

Indian Summer.

To the Editor of the SCIENTIFIC AMERICAN:

The author of the article on Indian summer in the SCIENTIFIC AMERICAN is in error when he supposes the Northern States and Canada have a monopoly of that delightful phenomenon. Earth has no more beautiful scenes than are beheld in the Southern and Gulf States in the Indian summer periods, especially in the region of the Blue Ridge Mountains. As I write this in a Southern Gulf town, the indescribable Indian summer haze hangs over town, prairie, and bay, although summer verdure is still unscathed.

ALEX WILLIAMS.

Port Lavaca, Texas, November 17, 1904.

HENRI BECQUEREL.

BY DANIEL BELLET.

Henri Becquerel first came prominently before the public when he began the investigation of phosphorescent and fluorescent substances shortly after the discovery of the X-rays, for the purpose of ascertaining whether their phenomena might not be attributed to causes similar to those which give rise to the properties of the Crookes tube. He found that they projected emanations entirely different in character—emanations which have been fittingly named "Becquerel rays."

Prof. Henri Becquerel is the grandson of a celebrated physicist, Antoine César Becquerel, and the son of an equally illustrious physicist, Alexandre Edmonde Becquerel. At present Henri Becquerel is professor of applied physics. When he first began his course of lectures in 1892, at the Museum, with characteristic modesty he never once referred to his own name in passing in review work of his predecessors, despite the fact that these predecessors were his father and his grandfather. His educational activities are not confined to the Museum, for he is actively engaged at the Conservatoire des Arts et Métiers, and is also one of the Chief Engineers of the Department des Ponts et Chaussées.

Born in 1852, Henri Becquerel entered the Ecole Polytechnique at the age of 20. The three years from 1874 to 1877 were spent at the Ecole des Ponts et Chaussées, a preparatory school in which the construction of roads and bridges and civil engineering in general is taught. Although an engineer by training, Becquerel was soon attracted to the study of pure science, following in the footsteps of his eminent grandfather and father. In 1878 he entered the Museum of Natural History, an institution with which the name of Becquerel will be ever linked. Since 1895 he has filled a professor's chair at the Ecole Polytechnique. He has been a member of the Academy of Sciences since 1889.

I did not have the pleasure of knowing Prof. Becquerel personally when I received the commission of interviewing him for the SCIENTIFIC AMERICAN. What struck me most when I first met him was his charming personality. He lives in one of the most aristocratic streets of Paris, in the Quartier des Champs Elysées, quite near the Arc de Triomphe et de l'Etoile. When I stepped into the reception room of his house, I marveled not a little at the artistic surroundings in which I found myself. And the reception room is but a counterpart of every room in the house. Every chamber through which I was conducted by Prof. Becquerel had its old furniture, its quaint bric-a-brac, its walls covered with pictures—many of them heirlooms and family relics handed down by Antoine César Becquerel. Although a scientist to his finger tips, Prof. Becquerel assured me that he takes a lively interest in the beautiful surroundings of his home, and the contemplation of pictures and statues is a diversion and a rest from the arduous work of the laboratory.

In person Becquerel is short. His face is wonderfully expressive and mobile. His diction is choice. Every word is selected with the care habitually given by a man of culture to literary form.

His laboratory work is admirably systematic. For weeks he experiments and observes the results of his experiments in accordance with a well-defined plan. Probably it would not be impossible for him to state far in advance what particular phase of scientific research would receive his attention on a certain day a year hence. And this systematic plan, which he has followed more or less throughout his entire career, may be considered a continuation of the work of his father and grandfather. Despite the fact that there is hardly a branch of pure science in which he has not made some important discovery, he has occupied himself chiefly with the problem of those mysterious luminous phenomena which his father before him had studied, and the solution of which his grandfather had dimly foreseen. It is this continuity of scientific purpose and investigation that lends so peculiar an interest to the labors of the Becquerel dynasty.

Henri Becquerel labored long and faithfully in the fields of electricity, magnetism, optics and meteorology; but the researches which he has carried on in these fields are really part of a well-defined system having for its object the study of electro-optic phenomena such as the invisible infra-red spectrum and the absorption of light. All his investigations have been carried on in the physical laboratory of the Museum of Natural History which was the scene of the labors of his father and grandfather before him. Starting with Faraday's splendid discovery of the relation of electro-magnetism to light, Becquerel succeeded in showing the existence of a fundamental relation between the rotary magnetic power of bodies and a very simple function of their index of refraction. The limitations of this article prevent me from following in detail the interesting development of Becquerel's theories. Hundreds of observations were made which lead to the conclusion that the phenomena of electro-magnetism are intimately connected with the speed of propagation of luminous waves, and to an inter-molecular magnetic action. Negative rotations in the plane of rotation of light were studied minutely, and clearly and simply explained. The Faraday phenomena were discovered in gases, an entirely new domain, by means of wonderfully ingenious and sensitive apparatus. The magnetic influence of the earth as part of this systematic plan of investigation was likewise studied, and the results obtained have fully confirmed the conclusions which have been inductively drawn by scientists. So far, indeed, were these investigations carried, that a method was devised for determining the rotary magnetic power of a body, and of ascertaining by simple optical measurements the absolute intensity of terrestrial magnetism. Naturally Becquerel was ready to approach from an entirely new standpoint the phenomena of atmospheric polarization, with the result that he had made discoveries that are ill described by the simple word "startling."

Becquerel's study of invisible infra-red radiations is not the least interesting work which he has accomplished. Here he followed directly in the footsteps of his father, who had discovered that these thermo-rays cause the phosphorescence of a substance which has been previously rendered luminous. This may be said in a measure to be the starting-point of the discovery of the radio-activity of matter. By projecting on a phosphorescent surface discontinuous spectra of incandescent metallic vapors, he discovered a series of rays, the existence of which had never been suspected. He was thus led to examine the invisible vapors of different metals. This opened up an entirely new field in spectroscopy.

Becquerel's interesting investigations of the absorption of light by various bodies brings us nearer to the subject of radio-activity; for the compounds of uranium were used in studying the phenomena of phosphorescence. He proved the variability of the spectra with the direction of the luminous vibrations by which they were traversed. All these researches led to a new method of spectrum analysis, based on the independence of the various substances of which a single crystal is composed, and rendering it possible to determine the structure of the crystal without fracture. It was this work that earned for him a place among the members of the Academy of Sciences. While continuing his studies of phosphorescence and light, he still found time to investigate fluorine.

Each discovery that he made seemed to foreshadow the next; for he seemed to sow the scientific fruit which he was to garner at a later day. Although in 1896 he began his interesting communications to the Academy of Sciences on the radiant properties of the salts of uranium, and although for two years he patiently made experiments on the emanations of uranium and its salts, it is somewhat remarkable that at the beginning of 1898 not a word is published in the reports of the Academy of his labors. The reason is to be found in the fact that he did not wish to publish immediately the discovery of phenomena which formed but a part of still vaster discoveries—discoveries which are now in course of publication, and which are concerned chiefly with Faraday and Zeeman phenomena.

It is impossible in the brief space at my disposal to enumerate all the discoveries which have been made by Prof. Becquerel. A modern scientific bibliography, however, would be very largely composed of studies bearing his name; they would include monographs of all kinds on radio-active substances and radio-activity.

It must not be forgotten that the work of M. and Mme. Curie, strikingly original though it may be, was nevertheless suggested by, and may be said to be an outgrowth of, Becquerel's investigations of uranium. Prof. Becquerel himself has only very recently published a voluminous treatise on the spontaneous radio-activity of matter, to which he has given the suggestive title "Researches on a New Property of Matter."

Results of the Annual Automobile Hill-Climbing Contest at Eagle Rock.

The fourth annual hill-climbing contest of the Automobile Club of New Jersey was held on Thanksgiving Day, November 24, at Eagle Rock hill in Orange. The cars were classified according to selling price, and also by weight. The fastest time was made by Bernin, who, on W. Gould Brokaw's 60-horse-power Renault racer, covered the mile up an average grade of about 12 per cent in 1 minute, 20 seconds, or at a speed of 45 miles an hour. William K. Vanderbilt, Jr., on his 90-horse-power Mercedes car, made the climb in 1 minute, 20 3-5 seconds; and two 90-horse-power Fiat racers, driven by William Wallace and Paul Sartori, secured third and fourth places in 1:22 and 1:22 1-5 respectively. These records were made in the contest for cars weighing from 1,432 to 2,204 pounds. In the contest for light cars, weighing between 851 and 1,432 pounds, Guy Vaughn, on a 40-horse-power Decauville, took first place in 1 minute, 37 1-5 seconds; while a 7½-horse-power Prescott steamer and a 15-horse-power White steamer made the second and third best times in 1:37 3-5 and 1:48 respectively. The same White machine made the best time in the contest for stock steam cars, this time being 1:23 3-5.

In the contests for gasoline machines of various prices, an Oldsmobile made the best time (3:06 1-5) for machines selling under $850, a Cadillac coming second in 4:33 2-5. The winner in the $850 to $1,250 class was a 22-horse-power Buick car, which made the climb in 2:18 2-5, and was followed by a 12-horse-power Duryea in 2:33 2-5 and two 15-horse power Elmores in 2:41 4-5 and 2:45 3-5. In the $1,250 to $2,000 class, first, second, and third places were secured by a 14-horse-power Columbia, a 12-horse-power Franklin, and a 16-horse-power Rambler in 3:14 2-5, 4:03 3-5, and 4:13 2-5. A 40-horse-power Thomas, representing machines in the $2,000 to $3,000 class, covered the mile in 2:42 4-5; while in the $3,000 to $5,000 class a 24 to 30-horse-power Walter car secured first in 1:54 2-5, and 24-horse-power Pope-Toledo and Matheson cars second and third in 2:15 4-5 and 2:21 4-5. It can thus be seen that some of the moderate-priced cars are just as good or even better hill-climbers than those of the larger and more expensive type. Of the cars valued at over $5,000, the best times were those stated above for heavy machines. It will be noted that all of these are foreign machines. The records for electrics were 4:22 3-5 by a 3-horse-power Torbensen machine and 5:23 2-5 by a Columbia. In the 551 to 851-pound class for gasoline cars, a Franklin did the climb in 2:26, and a Cameron in 3:07 1-5, both of these machines being of the air-cooled-motor type. The hill climb was the most successful one ever held at Eagle Rock, and it furnished an ample demonstration of the climbing ability of both American and foreign stock cars.

The Oldest Self-Striking Clock in the World.

In the north transept of Wells Cathedral, England, may be seen the oldest self-striking clock with a count-wheel in the world, having been constructed by Peter Lightfoot about 1320. This timepiece contains many devices which testify to the ancient horologist's ingenuity. Several celestial and terrestrial bodies are incorporated in interesting movement and relationship. They indicate the hours of the day, the age of the moon, and the position of the planets and the tides. When the clock strikes the hour, horsemen fully armed dash out of two gateways in opposite directions, and charge furiously. They strike with their lances as they pass, as many times as corresponds with the number of the hour. A little distance away is seated upon a high perch a quaint figure, which kicks the quarters on two bells placed beneath his feet, and strikes the hours on a bell. The dial of the clock is divided into twenty-four hours, and indicates the phases of the moon and a map of the heavens. Outside the transept is another large dial and two bells, on which two armored knights strike the quarters, each with his halbert, and are said to be actuated by the mechanism of the clock inside.

The National Mosquito Extermination Society.

The second annual convention of the above society is to be held on December 15 and 16 next in New York and Brooklyn. There are to be participants from abroad and all over the United States. Important measures are to be considered in reference to the extermination of the mosquito in the various States, and much interesting information is promised.

The society has recently issued its first annual Bulletin, which is full of useful facts and historical data relating to the work done during the past year.

THE CALIFORNIA REDWOOD IN MODERN ENGINEERING.

BY H. A. CRAFTS.

The California redwood (*Sequoia sempervirens*) has been chiefly celebrated in its primitive form of gigantic trees; its place in modern mechanics has not been so extensively dwelt upon. Yet at the same time the wood occupies an important position in the industries of the country, especially those of the Pacific slope.

While the use of redwood is large and increasing, the supply is limited. The principal field of supply extends along the Pacific coast from the northern boundary of California nearly to San Francisco Bay, and reaches inland only from ten to twelve miles. There is a limited area of redwoods south of San Francisco, but it does not count much in the general supply of lumber. Humboldt County in the north, which contains the larger redwood forests, has cut 52,000 acres of the wood, but still has left 486,000 acres. It is estimated that this acreage contains 49,000,000,000 feet of redwood lumber, which at the present rate of consumption, about 250,000,000 feet annually, would last about two centuries. More conservative estimates, based upon a broader knowledge of supply and demand and the probable increase in consumption, give only one century for the final exhaustion of the country's supply of redwood. As no measures are being employed with an idea of conserving the supply, this estimate will doubtless prove to have been pretty nearly correct.

The demand for redwood in the lumber trade is increasing. Its use is at present almost wholly confined to the Pacific slope, but the millmen of the coast are exerting themselves to push the material into the eastern markets, especially the market of Chicago. The redwood in a manufactured state has thus far been used in the East in the shape of shingles; but its adaptability to the manufacture of doors, sash, blinds, mantels, as well as to making of both exterior and interior finish, stave pipe, etc., will be demonstrated.

The uses to which the redwood is put in California are almost innumerable; but its employment in the manufacture and use in stave pipe and tanks is of special interest. The principal uses to which redwood stave pipe are put include domestic water supply, irrigation, water power, and outfall sewers. The pipe is slowly finding its way even into the more extreme East, the Excelsior Wooden Pipe Company, of San Francisco, having just secured the contract for installing a system of domestic water supply in Lynchburg, Va., which includes twenty miles of pipe of 30-inch internal diameter. The same company not long since installed a section of water-power pipe of the same wood at Cornell University, New York, of an internal diameter of 60 inches.



Redwood Pipe with Steel and Iron Elbows.

But it is in the great mining, irrigation, and domestic water supply operations of the Pacific slope that the more striking features of the use of redwood stave pipes and tanks are observable. The stave pipes vary in size from an internal diameter of eight inches to nine feet; while one manufacturing company has in contemplation the construction of a pipe to have an internal diameter of ten feet. The redwood tanks are used principally for the holding of water, but at the same time many are used for the storing of oil and wine, while they enter largely into the construction of cyanide plants for the separating of ores. In the construction of this class of tanks it is interesting to note that a former custom of building them larger at the bottom than at the top has become almost entirely obsolete, the modern tank being built in the shape of a perfect cylinder.

The larger stock tank has a capacity of 100,000 gallons. A tank of this capacity would have an outside diameter of 31 feet 9 inches and a height of 18 feet.

The larger-sized redwood stave is made in short sections, and the radii of the curves in the completed pipe lines are necessarily long. The radius of the ordinary curve in a ten-inch pipe is about 125 feet, while that of a nine-foot pipe is about 800 feet. In meeting sharp curves it is found necessary to introduce riveted steel elbows. In the smaller pipes, however, it is found pos-



Redwood Stave Pipe that has Supplanted an Irrigation Flume.

Two-foot Domestic Water Service Redwood Stave Pipe Showing Two-foot Gate.

Laying a Redwood Stave Water Pipe.

Three 54-inch Redwood Stave Pipes Used for Power Purposes.

CALIFORNIA REDWOOD IN MODERN ENGINEERING.



Exterior View of the Temple of the Columns, Mitla, Oaxaca, Mexico.



Facade of the Temple at Mitla. Below Appears the Obstructed Opening Leading into the Subterranean Chambers.



Ruins of the Great Pyramid Temple Called the "House of the Magician," Uxmal, Yucatan.



One of the Great Arched Doorways of the House of the Governor, Uxmal, Yucatan.



Aztec Sculpture Representing Two or More Deities of the Aztec Pantheon. Height, 10 Feet; Weight, 12 Tons.



The Ruin of a Small Temple on Cozumel Island, Eastern Yucatan.

Ruin of the Building Showing Remains of a Great Stucco Face, Nocuchich, Northern Yucatan.

THE ANCIENT RUINS OF YUCATAN AND MEXICO.—[See next page.]

sible to use cast-iron elbows. In constructing wood stave pipe around a curve, the staves are fitted together, partially banded, and then, by applying such power as the surrounding conditions will permit, the pipe is made to assume its desired shape. During the application of the power the staves are driven endwise, in order to close the butt joints. To bring the larger-sized pipe into proper curve, it is usually the custom to employ jack screws.

The use of the redwood stave pipe has been found especially favorable to hydraulic engineering in the West, because of its lightness and ease of transportation. For the construction of pipe lines in mountainous countries, remote from railroad transportation facilities, it fills the bill almost completely, for the reason that it can be carried in the "knocked-down" shape. If need be, the staves may be lashed to the backs of burros, and thus carried into places absolutely inaccessible to a vehicle of any kind. When thoroughly seasoned, the California redwood has a lighter specific gravity than almost any other known wood, weighing only about two and a half pounds to the board foot. The wood also possesses a great power of resisting decay, for the reason that it is very free from knots, seams, and pitch.

In the irrigated districts of the Pacific slope the use of redwood stave pipe is being largely employed in the conducting of water across deep canyons and gulches, taking the place of the old-fashioned trestled flume. Pipe thus employed usually does its work in the shape of an inverted siphon.

The manufacture of stave pipe is quite a simple process, the staves being turned out by an ordinary machine called a "sticker." The edges of the staves are of course cut on radial lines, and the sides on concentric circles that conform to the inside and outside radii of the pipe or tank under construction.

THE ANCIENT RACES OF YUCATAN AND MEXICO.—II.

BY RANDOLPH I. GEARE.

The number of ruined cities in Yucatan, and the State of Chiapas to the southeast, is very large. Two explorers alone discovered the remains of fifty-four ancient cities, including in Chiapas the wonderful remains at Ocozingo and Palenque, and in Yucatan the monumental ruins at Maxcanu, Uxmal, Sacbey, Izamal, Chichen, and a host of others, in the interior; and at Tuloom, Tancar, and on the island of Cozumel on its eastern coast. Among these the ruins of Palenque, Uxmal, and Chichen are among the most remarkable for their architectural forms and ornamentation, but they, as well as others represented by the illustrations, have been made so well known in these columns that it seems unnecessary to dwell on their characteristics in this article, which, as already indicated, is intended to deal rather with the people than with their buildings.

The men who built these cities were, as has been pointed out, far removed from the condition of nomadic tribes. Taste and luxury had long been grafted on the mere wants of the natives. They had learned to build, not only for protection against the elements, but for permanent residence. Here, however, as in Egypt, the remains are chiefly of temples, palaces, and tombs. The worship of God, the safety of the body after death, and obedience to authority, are demonstrated by the temple, tomb, and rock-built palace.

The country of the Aztecs, now called Mexico, was formerly known as Anahuac, a Toltec word signifying "situated near the water." At first this name was applied only to the Valley of Mexico, on account of its numerous lakes. When Grijalva in 1518 discovered the shores of Anahuac, the country was divided into four kingdoms, three republics, and a host of small states. Mexico was the chief kingdom; then came Colhuacan, Tlacopan, and Michoacan. The republics were Tlaxcala—whose citizens, for centuries enemies of the Aztecs, made common cause with Cortez—Cholula, and Huexotzinco.

When Europeans first landed in Mexico, they found a numerous race of people called Nahuas, or Aztecs, who had developed a civilization at once astounding and incomprehensible to the adventurers. Their industrial attainments were fully evidenced by their spacious temples and other large and elaborate structures, which to-day, in part at least, testify to their former greatness. Their principal community was at that time in the Valley of Mexico, although, according to tradition, the original home of the Aztecs was Aztlan, in or near the Gulf of California.

About the year 648 A. D., seven of the principal tribes of the great nation of the Nahuatlacs left their homes, advanced toward the valley of Anahuac, and subsequently returned. Many years later they set out again, crossed the modern province of Xalisco, following the course of the Tolotlan River, and stopped at Culiacan. Here Huitzilipochtli, the terrible god of war, demanded that they should build him a tabernacle, and that the priests should carry it. The Aztecs, special *protégés* of this god, were commanded to separate from their companions and to take the name of Mexi, in honor of their being favorite sons of Mexitli, which was another name of this war god.

The Aztecs for a long time led a sedentary life, while the Nahuan natives spread over Anahuac, and covered it with kingdoms. Thus divided and subdivided, the Nahuas were for centuries engaged in conflict with one another, resulting in the smaller states being annihilated by the larger, which in turn would perhaps have been absorbed by the Aztecs, had it not been for the advent of the Spaniards. Then leaving Culiacan, the Aztecs entered Colima, and went as far east as Tollan. Wandering ever in search of a final resting-place, they reached Tzompango ("place of bones"), a large city of the valley to which they were destined afterward to give their name of Mexicatls, and from which the word Mexico was later formed. Here they were sorely persecuted by one of the generals of the Chichimec king Xolotl, and they therefore sought refuge at Chapultepec, which belonged to the Colhuas. The Colhuas soon declared war against them, and the Aztecs were reduced to a state of slavery. After fighting successfully for their masters against the Xochimilcos, in the hope of regaining their liberty, they were treated worse than ever, and were finally ordered to leave the country. Their wanderings began again, and finally they settled (and this time permanently) near the lakes Tezcoco, Xochimilco, Chalco, and Xaltocan. Here in 1325 they founded the great city of Tenochtitlan, now the city of Mexico, where they reared huge temples and other buildings.

In appearance the Aztec was of medium height, thickset and well-proportioned. He had a narrow forehead, flat nose, black eyes, large mouth, thick purple lips, short regular teeth, well set in rose-colored gums. His hair was black, thick, and coarse, and his beard scanty. His skin was of a dull copper color.

South of Vera Cruz lies the State of Oaxaca, a region which also seems to have once been the seat of an advanced civilization. Interesting remains, including tumuli, are known to exist at Tachila, at Monte Alban, six miles from the city of Oaxaca, where there are



COMET "1904 A" AS SEEN MAY 19, 1904. 10 H. 19 M.

tumuli and pyramids, at Coyúla, at San Juan de los Cúes, at Guengola, at Quiotepec, and at Mitla. Most of these ruins present pyramidal shapes in combination with the vertical. The ruins of Mitla are perhaps the most interesting of all, with their monuments and palaces, which excite universal wonder and admiration for the power of this ancient people, giants in the art of building and decorating edifices of stupendous dimensions and of exceedingly ornate decoration. There it was that the Aztecs in 1494 finally subdued the natives, and it is supposed that large numbers of the unfortunate Zapotec inhabitants of Mitla and Huaxaca (or Oaxaca), who had previously become prisoners of Aheutzotl, swelled the splendid but brutal sacrifice of human victims with which the great temple of Mexico was dedicated in 1487.

The cruelty of the Mexican sacrifices of human beings has always been one of the principal arguments against the civilization theory of the Aztec race; but all religion includes the idea of sacrifice, and the Aztec sacrifice arose probably from a blended motive of propitiation and policy. The human sacrifices by that people were perhaps founded on the idea that the best way of getting rid of culprits, dangerous people, and prisoners of war taken in large numbers, and whom it was impracticable to support or retain in subjection, was to offer them to the gods. Viewed only in the light of their idolatry, it is difficult to account for their intellectual advancement in architecture and other industrial and artistic pursuits; but as the latter are readily demonstrated, it must be held that these manifestations of a system of advanced civilization prove their social condition to have been much more refined than their religion, from which we may conclude that the Valley of Anahuac, although a hotbed of priestcraft and superstition, was also the center of a cultivated society.

According to the reports of explorers, the chief object sought in the erection of the grand edifices at Mitla and elsewhere, was to preserve the remains of their princes; and it is alleged that at the death of a son or brother, the sovereign retired to this place, and taking up his residence in a portion of the building, performed religious services and indulged in ceremonious grief. Other reports say that these spacious though solitary abodes were inhabited by an association of priests who devoted their lives to expiatory services for the dead. Their isolated sites are certainly well adapted for any purpose of a gloomy nature; for, according to travelers, the silence of the lovely valleys is unbroken even by the songs of birds. A large portion of the valley, overlooked by a noble group of mountains, is said to be still covered with heaps indicating the sites of ancient architecture; but as most of the ground is under cultivation, every relic of the architecture at this point is destroyed, and even the ground-plans have become so indistinct as to make research useless. There is another lot of ruins at Mitla, however, consisting of four connected or nearly connected buildings, each fronting a cardinal point, and the whole inclosing a square court. They have been described in detail by several explorers, and the reader is referred to the literature for the facts concerning the ruins at this place and others, some of which are illustrated in this article from photographs secured by Mr. William H. Holmes in connection with his explorations of this highly interesting region in 1894-95.

Many accounts of the peopling of Mexico by the Aztecs have been written, most of which seem to agree in the main essentials, namely, that Yucatan and the territory of the Zapotecs were once inhabited by a refined people, who were later subordinated to the Aztecs by conquest; that regarding the settling of the Vale of Anahuac, the original inhabitants came from some unknown place "at the north," and in the fifth or eighth century, settled at Tollan or Tula, in the neighborhood of the Mexican Valley; that this spot became the parent hive of an industrious and progressive people, whose northern frames and characters were civilized and not emasculated by the more genial climate to which they migrated; that they cultivated the soil, built extensive cities, conquered their neighbors, and after performing their allotted task in the development of the continent, wasted away in the tenth or eleventh century under the desolation of famine and unsuccessful wars, the Toltec remnant emigrating southward; that during the next hundred years, the valleys and mountains of this beautiful region were nearly abandoned, until a rude tribe known as the Chichimecas came from the north, and settled among the ruins abandoned by the Toltecs; and that some years afterward several tribes of the Nahuatlacs reached the valley, announcing the approach of another band from the north, known as the Aztecs.

Thus it will be seen that wave after wave of population poured from the north into the valley till it was reached by the Aztecs, who about the year 1160 left their mysterious and unknown site at Aztlan. After one hundred and sixty-five years of wanderings they descried an eagle grasping in a claw a writhing serpent, and resting on a cactus which sprang from a rock in the Lake of Tezcoco. This had been designated by the Aztec oracles as the spot where the tribe should settle after its long and weary migration; and accordingly the city of Tenochtitlan (now the city of Mexico) was founded on the sacred rock, and like another Venice rose from the bosom of the placid waters.

COMET "1904 A."

M. L. Rudaux, who for some time past has been making some interesting discoveries and observations at his private observatory at Douville, France, has recently succeeded in photographing the new comet called "1904 A."

From the viewpoint of the discovery of this comet, the utility of astronomical photographs is clearly shown, since it was in a photograph enlarged eight and a half times that the discovery was made. On the other hand, this discovery brings into prominence the advantages to be gained by the use of simple portrait lenses for this kind of photography. The comet 1904 A was very faint and of about the 9th magnitude, and yet owing to the rapidity of the objective, it required a short exposure of but half an hour for the star to make a sharp impression upon the plate. Contrary to what usually occurs, the negative reveals scarcely any trace of tail, while direct observation shows a short fan-shaped one.

In the 4½-inch equatorial provided with a magnifying power of 45 diameters, the comet was difficult to see. At the outset, nothing was distinguished but a small nebulous mass and a brilliant nucleus. Afterward, there was perceived a wide fan-shaped appendage. The nucleus occupied internally the apex of a triangle formed by the fan, so that the front of the comet appeared to be pointed. The luminous intensity of the tail was seemingly produced by different sectors or, better, trains provided with a coma. Finally, the nucleus appeared to be multiple, but at instants solely, because of the great difficulty of observing it.

WAX FARMING IN CHINA—A STRANGE INDUSTRY.

BY WALTER L. BEASLEY.

Among the novel occupations in China but little known, if at all, to the outside world, is that of the wax farmer. The most remarkable feature in connection with this industry is that the owner's entire crop is produced by the free labor of myriads of little insects, whose eggs or cocoons deposited on the limbs and branches yield a rich harvest, which is transformed into pure white wax and marketed at a fair price. Equally odd and fantastic are the midnight journeys of the agile and sure-footed porters, who are forced to hurry along as fast as possible with their loads of insects on their backs hundreds of miles across steep and rocky mountain passes, ascending and descending precipitous places which no animal or conveyance could traverse with safety, in order to land their cargoes in proper time for the hatching-out season. The American Museum of Natural History has just received some specimens of the wax-covered branches taken from the field, and the only ones to reach this country so far. Photographs of the strange creature itself and other characteristic views are shown and described here for the first time.

Comparatively little is known of this peculiar and valuable insect. Prof. C. Saski, of the Agricultural College of the Imperial University of Japan, has just reported in a bulletin on the life habits of the wax-producing coccid (*Ericerus pela*, Westwood). He gives much detailed information as to the size, appearance, and breeding habits of the creature, the salient points of which are here incorporated to supplement the general narrative. Through the kindness of Prof. William Beutenmüller, of the Entomological Department, this has been placed at the disposal of the writer. The insect is more common in China, though it is also found in Japan. In both countries it selects different trees to feed upon. The food plant in China is *Fraxinus Chinensis*, while in Japan it is *Fraxinus pubentrois* and *Ligustrum ibata*.



Layers of Wax as Deposited by the Insect on the Branch.

The male has a head nearly triangular and of a light orange color; the dorsal surface is marked with a broad grayish-brown band. The antennæ are long and composed of ten segments, covered with hairs. The segments are long, except the two basal ones, which are shorter and stouter than the rest. The last segment has on its tip three digitules. The thorax is large, elongated, and broader than the head. The legs are comparatively long, light brown, and covered with grayish hairs. The first pair lie far apart from the others. The four wings are long oval, and quite transparent. The abdomen is of nearly equal length to the thorax, and its anterior segment is closely attached to the thorax by its entire breadth. From the side of the last abdominal segments there protrude two slender white filaments, which are much longer than the body. The length of these is 3 millimeters. The female is globular in form and 11 millimeters in diameter, and when found in aggregations is slightly deformed from mutual pressure. The dorsal part, which forms the larger portion of the body, is dark reddish brown in color. The ventral flattened surface is almost oval in shape, but its large central portion becomes gradually concave, as the eggs are deposited, and finally gets deeper and deeper, so as to form a large hollow space, wide enough to protect many thousand eggs. If the insect is removed from the stem, the eggs fall freely off. These are elongated oval, light yellow, with diameters of 0.432 millimeter and 0.216 millimeter. The female begins to lay eggs about May 1, and the young larvæ commence to hatch out at the beginning of June. They are long oval, of an orange yellow color. The larvæ distribute by crawling about over every branch, and after molting pass to the second stage of growth. In the last part of August the male larvæ of the second stage are completely imprisoned within an oval cocoon, formed by snowy-white filaments, secreted by the dermal glands. Usually large numbers of the oval flattened cocoons completely surround the stems and branches. Within these the larvæ pass from the second to the third stage. At this period the antennæ, wings, and legs are all free, and the length of the body is 2.2 millimeters. A few days after remaining in this state, the winged insect appears through a slit-like opening at the free edge of the cocoon. The females go through the same stages of molting, and vary but slightly in structure and size from the male. The males appear about the last of September or beginning of October, and flit around the young females, who are already attached to the stems and branches.



Temple Candles made from White Wax.

The tree (*Ligustrum lucidum*) which produces the white wax insect grows in the Chien Chang valley in the western part of China, which is some 5,000 feet above the level of the sea. In March round brown forms are seen attached to the limbs and branches. If one of these should be opened, it would be found to contain innumerable white insects. By a strange law the insect will not flourish or produce wax in its birthplace, and if allowed to remain will drop off in a dead mass. The Chinese, with clever instinct, have discovered the exact locality where they will flourish to the best advantage, and have started breeding the insect and cultivating the particular food plant upon which it thrives and deposits the wax-making cocoons. Transporting the females to the various farming places some two to four hundred miles distant in the Province of Sze-Chuan gives employment during the season to thousands of porters. One of these wax-making centers is Kiating. About the first of May the female is nearly grown, and the body is almost conical, with a round base. Later on it becomes mature, and begins to deposit eggs. At this time the operation of removing the females from the limbs and branches to which they are attached and getting them ready to turn over to the porter for transit is commenced. They are thereafter carried hundreds of miles distant, to where the wax farmers have rows of the special food plant—a species of flowering ash five or six feet high (*Fraxinus chinensis*) upon which the insects feed and deposit their layers of wax. The insects are first tied up in a leaf of the wood-oil tree. A number are then placed in a gourd-like receptacle. These are then packed into two large bamboo baskets, and carried suspended on the shoulders. Many thousands of insects are taken in this way by each man on a trip. The porters have to travel entirely at night with their delicate and precious loads, for the mid-day heat would be dangerous to the lives of the inmates, as it would have a tendency to develop them too fast. It is customary, as the season approaches when the wax messengers are due, for the various cities and villages along the route to leave the gates open, so as to afford free and unobstructed passageway to the carriers. Seen at night running with all their might, dressed in most cases in rainproof straw, their flickering lanterns swaying to and fro with the motion of their bodies, they form a weird and picturesque sight. On they go, traversing rocky paths and lofty ascents of the Sze-Chuan Mountains, never stopping until the break of day, when they huddle up under cover of a shady retreat, where their baskets can be protected from the heat. They then prepare their meals, and await the coming of the night to continue their lonely and tiresome journey. On reaching their destination they immediately go to their masters or other agents, who have been awaiting their arrival. The baskets of insects are forthwith distributed to the respective farmers, who proceed at once to place them upon the food plant. They are tied on the branches in small bags made of leaves, where the heat of the sun hatches them. Holes are made in the leaves of the bags in which they are enveloped with a blunt needle, so that the insects may find their way out. When first hatched they creep rapidly up to the leaves of the food plant, where they nestle for nearly two weeks. After this they begin to scatter, and crawl along the branches.



Female Wax-making Insect and Eggs.

Night Porter Carrying Wax-making Insects to Breeding Place.

The females, after a short period, begin to lay their eggs, and the males deposit white cocoons, which in time completely coat every branch and stem. It is the cocoon of the male which yields the wax. By the first of September the whole tree is literally covered with layers of pure white wax a quarter of an inch thick. This is a beautiful sight, and were it not for the temperature of the air, one might readily imagine there had been a recent snowstorm in the vicinity. The farmers cut off the branches, and scrape them. The material is heated, strained, and turned into molds of different sizes, becoming pure, white, and hard. The cultivation and preparation for market furnishes employment for a large number of industrial workers, who convert the wax into candles for house and street lanterns, also for the making of temple images and other articles connected with ceremonial worship. It is also used as a polish for furniture and for imparting gloss to silk. A tax tribute of this white wax from the Province of Sze-Chuan is sent every year to Peking. The whole output of the various wax farmers is estimated to amount to about $200,000 annually. It is said that the process is very old, over six hundred years or more, being handed down from one of the ancient dynasties.

RECENTLY PATENTED INVENTIONS.

Of General Interest.

SHIELD TUNNEL CONSTRUCTION.—W. I. AIMS, New York, N. Y. The invention relates to tunnel construction in the bed of waterways and other places, the object being to provide a construction arranged to permit of driving the shield readily through sand, gravel, and other loose material, to protect the workmen in the shield in case of a sudden inflow of water or loose material by closing doors in the shield, and to allow of conveniently and quickly placing the sections of metal lining for tunnel in position.

MANUFACTURE OF PLATES FOR PRINTING.—E. A. NEBEN, New York, N. Y. The invention relates to the art of preparing relief-plates for printing typographically therefrom. The object is to provide certain improvements in the manufacture of plates, whereby zinc or copper plates are produced for receiving any desired design in half-tone effects, together with the necessary contrasts of high lights, solids, and shades to allow of using the plates for reproduction of color-work for fine color-printing.

TRUCK.—H. C. HARRINGTON and W. M. TOWERS, Rome, Ga. It is a very difficult matter to handle sacks of grain or heavy casks of merchandise with the ordinary truck from the fact that in loading material the pressure backward is very great, and unless the truck is held in position by an extra hand it will often slip backward, dumping the load and causing reloading. The improvement seeks to prevent any backward movement of wheels when truck is in position to receive load until the truck is adjusted out of such position toward a position for carrying the load.

Machines and Mechanical Devices.

BREAD-MAKING APPARATUS.—E. D. LYNDS, Newman, Ill. One object of this invention, among others, is to provide a novel construction for mixing flour and milk, water, or other liquid constituent through the aid of a rapidly-revolving disk, from which the liquid element will be discharged in a finely-divided state into the flour, and thoroughly mixed with the flour in the mixing-chamber.

MUSIC-LEAF TURNER.—N. P. JENSEN, Ephraim, Utah. The object here is to provide a turner for use on pianos, organs, music-racks, and the like, and arranged to permit of conveniently turning the leaves successively over in either direction to permit of operating the device either by hand or foot, and in the latter case to render the device especially serviceable for use on portable racks such as used by band-musicians.

Pertaining to Vehicles.

BRICK-ELEVATING ATTACHMENT FOR TRUCKS.—S. P. HEDGES, Greenport, N. Y. The invention relates to an attachment for trucks, especially trucks for carrying brick and other material to be burned, stacked, stored, or dried. The purpose is to provide stationary uprights and a movable frame mounted between them and adapted to carry pallets on which material is placed and to so construct the truck and carrying-frame that they will be more substantial than ordinary, being built with the least number of posts and posts not liable to bend or get out of shape.

Prime Movers and Their Accessories.

WIND-WHEEL.—E. PAVÓN Y MORALEDA, Madrid, Spain. The object of the inventor is to provide a construction whereby the wheel will not be bound or locked at any time by the action of the wind, as when one blade is in position to receive the pressure of the wind the blade in front will be free to spill the wind, thus preventing the wheel from remaining stationary by reason of the wind blowing in an angular pocket having fixed walls.

Railways and Their Accessories.

CAR-COUPLING.—R. REARDON, Savannah, Ga. This improvement relates to automatic double-knuckle car-couplers. The objects are to provide for insuring the certainty of action of a coupling of the type mentioned, for providing an absolutely secure coupling, and for providing means for quickly and easily uncoupling the device by automatic action when the locking device is operated to unlock the knuckle. The invention is an improvement upon a previous patent granted to Mr. Reardon, and it has been successfully used on the Atlantic Coast Line R. R.

RAIL-JOINT FASTENER.—J. A. GOSSARD, JR., South Solon, Ohio. The object in this instance is to provide details of construction for a fastener which are adapted to be placed in position for securing together two meeting ends of track-rails under spring tension of parts of the fastener by use of suitable tools or be removed by the same means, as occasion may require, a further object being to provide a fastener that is held in place for connection of the rail ends and their lateral support at joint by spring tension of its parts only and is devoid of bolts and nuts usually employed.

MONORAIL TRACTION.—C. E. FAROUX, 106 Rue de Courcelles, Levallois-Perret, Seine, France. This invention has for its object a method of and means for monorail traction whereby high speeds may be attained under good economical and practical conditions. The device comprises a single rail of suitable section, upon which travels the locomotor-vehicle, which rests upon a truck. The invention comprises a vehicle including a body, flanged wheels supporting the body, a rail having inclined sides with which the wheel-flanges engage at two points only, guide-wheels bearing on the upper edge of the rail, a track above the vehicle, and wheels carried by the vehicle and engaging the opposite sides of the last-named rail.

Designs.

DESIGN FOR A CULINARY VESSEL.—F. H. GRISWOLD, Springfield, Mass. The design is applied to an open kettle or vessel for cooking fruits, meats, and vegetables. The body enlarges from the bottom up, and on the same near the bottom, is a series of like figures, in low relief or intaglio, each comprising a series of rays radiating upward from a common point where the capital letter X is located, the whole indicating "X rays."

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. **In every case it is necessary to give the number of the inquiry.**

MUNN & CO.

Marine Iron Works. Chicago. Catalogue free.

Inquiry No. 6242.—For parties to manufacture, on contract, small machines weighing 6 pounds.

AUTOS.—Duryea Power Co., Reading, Pa.

Inquiry No. 6243.—For the address of the manufacturers of the wire-wound wooden pipe, in the United States and Canada.

"U. S." Metal Polish. Indianapolis. Samples free.

Inquiry No. 6244.—For makers of round, woven wire belting or round chain belting, sizes from ¼ inch to ⅛ inch diameter.

Perforated Metals, Harrington & King Perforating Co., Chicago.

Inquiry No. 6245.—Wanted, to purchase a good patent or novelty suitable for mail order business.

Handle & Spoke Mchy. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

Inquiry No. 6246.—For information as to process of making rubber stamps without steam heat.

If it is a paper tube we can supply it. Textile Tube Company, Fall River, Mass.

Inquiry No. 6247.—For makers of high-grade tools for school use,

Adding, multiplying and dividing machine, all in one. Felt & Tarrant Mfg. Co., Chicago.

Inquiry No. 6248.—For parties controlling the sale of the Belden trip hammers, or for the makers thereof.

Sawmill machinery and outfits manufactured by the Lane Mfg. Co., Box 13, Montpelier, Vt.

Inquiry No. 6249.—For makers of hydraulic presses with surface about 36 x 56 with moving stroke of about 2 inches or 3 inches only.

Thermo-piles for electrolytic assays and direct-current work. $3 each. Walsh's Sons & Co., Newark, N. J.

Inquiry No. 6250.—For small, simple machines for gluning, spinning and weaving cotton.

Leyden Chemical Works. Sole manufacturers of all luminous preparations. 688 East 182d Street, New York.

Inquiry No. 6251.—For the makers of the Cheeseman roller gin, or any other make of roller gin.

If you wish to buy patents on inventions or sell them, write Chas. A. Scott, 340 Cutler Building, Rochester, N. Y.

Inquiry No. 6252.—For makers of vane cutters and other machinery for manufacturing baskets and berry boxes.

We manufacture tripoli stones of all dimensions, disc, cylinders, etc., samples free. Seneca Filter Co., Seneca, Mo.

Inquiry No. 6253.—For manufacturers of dynamos.

We manufacture anything in metal. Patented articles, metal stamping, dies, screw mach. work, etc. Metal Novelty Works, 43 Canal Street, Chicago.

Inquiry No. 6254.—For makers of simple, up-to-date machines for boring iron pump cylinders.

Patented inventions of brass, bronze, composition or aluminum construction placed on market. Write to American Brass Foundry Co., Hyde Park, Mass.

Inquiry No. 6255.—For parties engaged in all kinds of spring work.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Machine Company, Foot of East 138th Street, New York.

Inquiry No. 6256.—For the address of the manufacturers of the Hadfield apparatus for treating disease by vacuum.

LIVE MAN WANTED.—If you have $5,000 and want $1,000 yearly in manufacturing business. Big demand, no competition. Write Manufacturing, Box 773, N. Y.

Inquiry No. 6257. For parties making machinery for manufacturing wood alcohol.

Manufacturers of patent articles, dies, metal stamping, screw machine work, hardware specialties, machinery and tools. Quadriga Manufacturing Company, 18 South Canal Street, Chicago.

The SCIENTIFIC AMERICAN SUPPLEMENT is publishing a practical series of illustrated articles on experimental electro-chemistry by N. Monroe Hopkins.

PATENT ON PUZZLE.—Manufactured cheaply, carried in vest-pocket. Wish to place with manufacturer to make and market on liberal terms. Chas. Henry, 3265 16th Street, San Francisco, Cal.

WANTED.—Pattern and model makers by a western manufacturer of hardware specialties. Must be first-class workmen. Young men ambitious to excel preferred. Model Maker, Box 773, New York.

PATENT FOR SALE.—Quick acting safety, double chain car brake, used and endorsed by R. E. Binning, Chief Electrician of the Union Railway Co. of New York. Address Safety Brake, Box 773, New York.

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(9486) A. H. S. asks: Theoretically, a rifle ball (or any body) fired vertically should return with exactly the same force. Practically, anyone who has tried, knows that a ball capable of a penetration of say four inches of wood at the muzzle will hardly more than dent the same wood on return. Please explain. A. The resistance of the air, which is very great in a body with a high velocity, prevents a rifle ball from rising as high into the air as it otherwise would, and hence it does not have as far to fall as its velocity on leaving the gun would indicate. The air also retards its fall, hence it does not acquire as great a velocity in falling as the height from which it falls would require. Both in ascending and descending its velocity is reduced, and hence its force on reaching the ground is much less than the velocity with which it left the muzzle of the gun.

(9487) H. H. asks: 1. Is the horse-power of a motor calculated the same as the horse-power of a steam engine? A. The horse-power of an electric motor is calculated by multiplying the volts and amperes together, and dividing the product by 746. 2. We have a circuit carrying 100 volts through 5,000 ohms resistance; if we add 1,000 ohms more to the circuit, how much more voltage will we have to have in order to have the same results at the end of the circuit? A. If you have 100 volts acting through 5,000 ohms resistance, you have 1-50 ampere flowing. To have the same through 6,000 ohms you will require 120 volts pressure. First case: $C = E \div R$; or $100 \div 5{,}000 = 1\text{-}50$. Second case: $E = C\ R$; or $1\text{-}50 \times 6{,}000 = 120$.

(9488) G. A. B. asks: We should like to get your valued opinion on a discussion with reference to sharp turns made by *vehicles in general*, and shall feel greatly obliged if you will submit your answer in the next issue of your paper. A contends that when an automobile makes a sharp turn, the outer wheels leave the ground, and the weight is all on the inner wheels; whereas B claims the inner wheels rise, and the weight is on the outer wheels; as proof, he offers as example the toboggan slide, where a person is thrown toward the outer end when it makes many turns. A. The centrifugal force developed by a vehicle in turning a corner causes the wheels to press outward, and the vehicle to overturn if the velocity is sufficient to throw it over. It is inconceivable that a force directed *outward* should cause the vehicle to be upset *inward*, or toward the center of the curve. To offset the outward pressure of a train, the outside rail is raised on curves in building railroads, as can be easily seen by looking at the elevated tracks in the city. The elevation is calculated to be sufficient to render the pressure on the inner rail again equal to that upon the outer rail; to tip the train in again, enough to balance the effect of the centrifugal force in tipping the train outward, and tending to upset the cars toward the outside of the curve. In bicycle tracks, where the vehicles often take the curves at high speeds, this elevation of the outer side of the track is very great, and in addition to this the rider finds it necessary to lean in a great deal, to balance the tendency to upset toward the outside.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending November 22, 1904

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.

Acid, preparing dialkylbarbituric, M. Engelmann 775,809, 775,810
Agricultural implement, H. H. Herred, Jr. 775,770
Air brake connection pipe joint, S. Feust.. 775,769
Air brake controlling apparatus, W. J. Schlacks 775,313
Air brake safety device. C. E. Cozzens.... 775,670
Animal trap, W. H. Harden..... 775,750
Ash can, J. H. Chidister 775,894
Autocar dust guard, W. H. Brown..... 775,595
Automatic gate, M. K. Lewis..... 775,756
Automatic lubricator, J. Farley..... 775,673
Back and head rest, invalid, L. R. White. 775,48.
Barium hydrate, manufacture of, F. Jahn.. 775,752
Barrels, etc., false partition for, E. E. Seacrist 775,610
Battery charging apparatus, H. G. Pape.... 775,732
Bearing, carriage, L. Myers 775,338
Bearing, roller, L. Villatte 775,875
Beater or movement apparatus, A. Fernander 775,813
Bed, couch, R. J. Wagner 775,876
Bed, invalid, J. W. Crigler 775,520
Belt cutter, punch, and link clencher, combined, L. Goldberger 775,419
Biscuit coating machine, sandwich, G. S. Baker 775,642
Blotter, D. Sarason 775,478
Bodkin, A. W. & I. R. Smith..... 775,882
Boiler. See Water tube boiler.
Boilers, etc., spring clamp or holder for lids or covers of pudding, D. Macfarlane 775,663
Book, manifold, A. Levison 775,833
Boot or shoe filler or form, A. Lewis..... 775,571
Boring bar, J. Riddell 775,459
Bottle, G. P. Dence 775,802
Bottle filling machine, Ortmann & Herbst. 775,307
Bottle, non-refillable, W. B. Hargan 775,650
Bottle, non-refillable, J. F. Spitt 775,786
Bottle stopper, G. W. Wheeler 775,411
Bottle stopper, M. Elfstrand 775,899
Box blank making machine, E. E. Flora.. 775,622
Brake, W. T. Stewart 775,638
Brake rigging, J. M. Davies, Jr..... 775,720
Brewing, J. Schneible 775,780
Brick cement and glaze, fire, Pressel & Fisher 775,384
Brick or tile cutting machine, W. R. Cunningham 775,800
Brick, paving, A. F. Knobloch 775,905
Brick, refractory, W. F. E. Berger..... 775,887
Broom fountain attachment, J. W. Shroyer. 775,460
Brush, B. A. Capehart 775,596
Brush drip, W. Dunbar 775,526
Brush machine, rotary, R. Y. Yeomans... 775,790
Buckle, A. Steiner 775,688
Buggy boot spring, W. R. Bradford..... 775,344
Building block forming presses, lowering stand for, G. H. Denton 775,347
Building blocks from material including hydraulic cement, manufacturing, H. Warden 775,588
Building structure, L. P. Hazen..... 775,703
Burglar alarm, electric, A. Getto 775,723
Butcher's stay, Baumgart & Moller..... 775,619
Button, S. M. Merrill 775,375
Button, J. V. Pilcher 775,457
Button, collar, H. T. Murphy..... 775,607
Cabinet, Bigelow & Hullhorst 775,594
Cabinet maker's clamp, H. Jorgensen.... 775,659
Cabinet, sanitary, S. L. Stuart 775,410
Calculating machine, J. G. Zollman..... 775,667
Calender-roll, F. R. Beck 775,438
Camera, folding pocket and focal plane shutter, J. S. Wright 775,437
Camping outfit, D. T. Abercrombie..... 775,766
Can body forming and side seam soldering machine, combined, Williams & Leavitt 775,880
Can body machine, locked seam, J. H. McElroy 775,340
Can capping machine, C. B. McDonald.... 775,339
Car, F. E. Hobbs 775,490
Car body and truck, E. S. Bennett 775,644
Car coupling, C. F. Christy 775,598
Car coupling, W. F. Wendt 775,789
Car coupling, P. Hien 775,902
Car door lock, vestibule, A. W. Zimmerman 775,617
Car draft rigging, railway, W. H. Miner.. 775,606
Car fender, street, J. M. Wilderman..... 775,358
Car for single rail elevated railways, F. B. Behr 775,743
Car, miner's, W. J. Neilson 775,778
Car replacer, H. J. Campbell 775,441
Car replacer, D. B. Ketts 775,705
Car seat, F. K. Fassett 775,528
Car step, folding, J. A. Kratz 775,366
Car swinging doors, actuating device for freight, D. A. Hitchcock 775,402
Car underframing, Williamson & Pries, 775,484, 775,485
Car underframing, railway, G. I. King... 775,301
Cars, crane attachment for loading or unloading, J. Leightham 775,832
Carbureter, explosive engine, G. F. Swain. 775,614
Carbureter, hydrocarbon engine, Burton & Seibel 775,553
Carbureting means, air, W. H. & G. E. Russell 775,859
Card clothing strickle, H. L. Miller..... 775,842
Carding engine drawing off device, D. S. Eastwood 775,804
Carriage top bow spring protector, C. H. Sooy 775,583
Carrier. See Trace carrier.
Cash register with distant indication, W. H. Muzzy 775,380
Caster, A. C. Stebbins 775,584
Cement, burning, M. Williams 775,693
Cement kiln, rotary, T. A. Edison..... 775,600
Centrifugal machine, A. C. Van Kirk.... 775,320
Centrifugal separator, J. J. Berrigan.... 775,415
Chain connecting device, C. E. Smith..... 775,355
Check, record book, and binder, bank, M. A. Howe 775,821
Chimney soot collector, C. Prangemeier.. 775,500
Chipping machine, F. B. Philbrick..... 775,382
Churn, S. F. McClane 775,848
Circuit controller, A. D. Scott..... 775,665
Circuit controller, electromagnetic, Vogel & Morrison 775,692
Clamping device, L. P. Halladay 775,399
Clamping device, E. V. Beddy 775,515
Clothes line support, H. J. Merz 775,760
Clothes pin, A. C. French 775,561
Clutch operating mechanism for cut-offs, P. B. Clarke 775,345
Clutch or coupling, friction, H. D. Loria.. 775,757
Coat adjuster, J. W. Beam 775,508
Coating machine, C. B. Wisner 775,694
Coffee machine, S. Sternau, et al..... 775,431
Coil spring, T. A. Shea 775,582
Coin controlled slot or vending machine and coin testing mechanism therefor, L. J. Disser 775,671
Column, R. Hegener 775,489
Column, wood, J. W. Hartmann..... 775,365
Columns, etc., binding device for, J. W. Hartmann 775,351
Compound engine, G. W. Sutcliffe..... 775,318
Compress, J. Shipway 775,611
Compressors, etc., regulator for, R. Conrader 775,398
Concrete wall molding apparatus, Shute & Henschen 775,666, 775,685
Condenser, variable air gap, F. F. Strong.. 775,871
Controller, E. Schattner 775,501
Convertible chair, E. L. Thompson.775,387, 775,388
Cooker and presser, steam, A. J. Ketelsen.. 775,827
Cooling heated surfaces, means for, Sager & Green 775,860
Copper or like metals from their ores, separating, P. & A. Weiller 775,548
Corn protector, J. Degen 775,897
Corrugating apparatus, J. A. McConnell .. 775,495
Cotton chopper, T. J. Hollingsworth..... 775,533
Cotton chopper, J. A. Hegue..... 775,771
Cotton picking machine, G. A. Lowry.... 775,451
Cotton picking machine, J. F. O'Shaughnessy 775,456
Cotton press, A. D. Thomas 775,481
Coupling, J. & J. O. Timms..... 775,615
Covering, weatherproof, Rugen & Abraham 775,636
Coverings, apparatus for making non-conducting, J. A. McConnell, 775,538, 775,539, 775,849
Coverings, making non-conducting, J. A. McConnell 775,494
Crate, banana, E. E. & M. B. Hogeboom. 775,491
Cream separator regulating device, J. J. Berrigan 775,467
Creamer, centrifugal, F. J. Arend. 775,464, 775,487
Cultivator, A. H. Kopperud 775,906
Cup. See Grease cup.
Curb, G. S. Du Fossat 775,623
Curb, gutter, and drain block, A. Austin.. 775,791
Current distribution system, alternating, A. E. W. Meissner 775,535
Current motor, alternating, E. J. Berg.... 775,439
Damper regulator, J. D. Bowne..... 775,468
Decoy, W. Riggs 775,545
Decoy duck, W. Riggs 775,580
Desk, wall, W. E. Burks 775,646

Detachable handle, W. I. Lyon 775,662
Die, G. Keppler 775,826
Die press, A. W. & A. H. Roovers..... 775,354
Door fastener, sliding, A. W. Zimmerman 775,618
Door, sidewalk, E. Johnson 775,425
Doubling and twisting machine, yarn, B. S. Allen 775,550
Dowel pin making machine, C. F. Stewart. 775,432
Draft equalizer, W. J. Robinson..... 775,312
Draft equalizer, N. N. Egge 775,748
Drawing and twisting or spinning worsted or other yarns, mechanism for, S. Sykes 775,690
Dredge, chain sand, R. Smith..... 775,686
Drier, Andrews & Loewenthal 775,717
Drying machine, Procter & Schwartz.... 775,763
Drop light, V. A. Menuez 775,304
Drum, E. T. Turney 775,711
Drum snare strainer, E. T. Turney..... 775,712
Dust separator and collector, C. McVeety.. 775,664
Dye, blue anthracene, M. Kugel 775,368
Dye, dark blue sulfur, A. L. Laska..... 775,570
Dye, green anthracene, M. Kugel..... 775,367
Dye, green blue anthraquinone, M. Kugel.. 775,369
Dyeing, etc., apparatus for, A. Fankhauser, et al 775,621
Electric circuit controlling switch, M. W. Day 775,445
Electric controller, Smith & Lippert..... 775,317
Electric current generating apparatus, C. S. Bradley.... 775,891
Electric furnace, A. C. Higgins..... 775,654
Electric heater, E. P. Weggen..... 775,714
Electric machinery, dynamo, H. G. Reist, 775,458, 775,857
Electric machines, regulating dynamo, W. L. Merrill 775,453
Electric motor, alternating current, B. G. Lamme 775,334
Electric time switch, C. S. Moore..... 775,844
Electric transmission system, C. G. & E. J. Burke 775,416
Electrical energy, converting fuel energy into, H. Jone 775,472
Electrical register and system therefor, L. A. Schmidt 775,408
Electromagnetic brake, R. C. Lowry, 775,834, 775,835
Elevator safety stop, Robinson & Casey.... 775,608
Engine bushing, tandem compound, J. Metzger 775,376
Engine speed regulator, explosive, J. S. Losch 775,908
Engine stop, J. H. Cary 775,329
Engines, incandescent igniter for explosive, P. J. Shouvlin 775,385
Eraser, F. W. Warren 775,616
Evaporating apparatus, vacuum, C. Ordway 775,577
Evening and grading machine, E. P. Nichols, reissue 12,288
Exercising device, R. Patterson..... 775,309
Exercising machine, F. Bitter 775,718
Explosive engine, P. Schmit 775,314
Explosive engine, C. & W. Hibbard 775,819
Extension table, J. Mitchell 775,377
Eyeglasses, L. Kirsch 775,828
Fabric coating machine, J. H. Shugg 775,684
Fanning mill, L. T. Larson 775,755
Farm gate, W. B. Miller 775,536
Fastener or holding device, G. A. Danielson. 775,801
Fastening device, J. F. Werle 775,433
Feed water regulator, W. A. Garrigus 775,396
Feed water regulator, steam boiler, Woods & Graves 775,412
Feeder, automatic boiler, N. F. Roadhouse.. 775,682
Fence, J. A. Le Hew 775,335
Fence, H. Meinecke 775,759
Fence post, E. Bruley 775,518
Fence post, A. F. Weissinger 775,715
Fender. See Car fender.
Fertilizer distributor, T. J. Waddell 775,357
File, paper, C. E. Shell 775,430
File, paper, M. G. Bristow 775,645
Filter, Mehnert & Pape 775,475
Filter, oil, R. K. Williams 775,323
Fire escape, M. A. Kiernan 775,604
Fire escape, O. B. Howe 775,704
Fire extinguishing sprinkler, automatic, G. Mills 775,729
Fire shield for proscenium arch openings of theaters, H. M. Smith 775,865
Fireproof covering for columns or pillars, S. Golliek 775,562
Fireproof flooring, D. W. Boyd 775,516
Fish hook, W. E. Koch 775,727
Fish trap, A. L. Brooks 775,388
Fluid tank indicator, Rantz & Collin 775,544
Flushing device, A. C. Davidson 775,719
Forces due to inertia and weight of valve gear, device for relieving, L. D. Lovekin 775,573
Fruit picker, J. W. Buchanan 775,519
Furnace reversing valve, S. M. Guss 775,563
Furniture, article of, G. W. Bent 775,466
Fuse, projectile, J. B. Semple 775,861
Galvanic element or battery, P. Brandt .. 775,892
Game register, F. H. Smith 775,864
Garment supporter, M. P. Zinderf 775,882
Gas burner, atmospheric, F. Gross 775,470
Gas generator, H. Weigle 775,641
Gas generator, acetylene, E. R. Cook 775,700
Gas meter protective valve coupling, F. L. Finnegan 775,648
Gas purifier, centrifugal, A. Steinbart.... 775,462
Gas purifier, centrifugal, F. V. Matton 775,758
Gasolene light generating machine, T. A. Davis 775,746
Gate, G. F. Moors 775,306
Gear, change speed, Seames & Langdon-Davies 775,503
Gear, drive, A. Mills 775,476
Gear mechinism for machine tools, change, W. T. S. Johnson 775,471
Gin rib, L. W. Ellman 775,349
Glass, chipping, P. J. Handel 775,818
Glass grinding machine, Geehring & Troche 775,816
Glass manufacturing apparatus, Wilson & Dull 775,740
Glassware, machine for making hollow, G. C. Pyle 775,709
Globe, collapsible, R. D. Gallagher, Jr..... 775,364
Goggles, motor, H. Newbold 775,381
Gold from ores, extracting, H. R. Cassel... 775,597
Governor, explosive engine, C. & W. Hibbard 775,820
Grain binder attachment, H. C. Raesner .. 775,341
Grain drill distributor, F. R. Packham ... 775,851
Grain separator and dust collector, combined, E. R. Draver 775,418
Grate, E. R. Cahoone 775,328
Grate operating appliance, G. A. Ellis 775,395
Grease cup, F. H. Bogart 775,697
Grinding machine spout, C. H. Norton.... 775,708
Hackling machine for flax, R. H. S. Reade et al. 775,352
Hammer, pneumatic, C. J. Smith .. 775,784, 775,863
Hand brake, H. B. Vickers 775,713
Hat pressing machine attachment, W. H. Kendall 775,825
Hatches, trap doors, etc., apparatus for operating armored, W. B. Cowles 775,768
Hay or grain loader or unloader, W. Kouns. 775,773
Hay press, E. A. Smith 775,612
Hay rake and elevator, Irish & Hoover... 775,751
Head gate, floating weir, Hart & Fairall.. 775,532
Heater and mixing faucet, L. M. Hooper... 775,655
High frequency apparatus, portable, F. F. Strong 775,869, 775,870
Hoe, J. J. Coston 775,701
Honey or section boxes from hives, apparatus for removing, J. N. M. & M. de Valdivielso 775,691
Hook. See Fish hook.
Horse detacher, W. T. Dunbar 775,803
Hose supporter, Tooker & Price 775,587
Hydraulic press, Philipp & Trentzsch..... 775,853
Index and receptacle, card, F. D. Belknap. 775,696
Index, map, E. Heubach 775,401
Inking mechanism, C. P. Byrd 775,698
Insulated rail joint, G. A. Weber 775,322
Insulating support for electric third rails, W. H. Barnard 775,592
Insulator support, E. H. Fairbanks 775,812
Journal bearing, H. V. Kuhlman 775,660
Journal box, A. B. Gardella 775,447
Journal box, dust proof, J. A. Kennedy ... 775,566
Journal lubricating device, J. J. Moss 775,730
Keir, vomiting, E. D. Jefferson 775,450
Knitting machine cam device, lamb, W. Bach 775,742
Lace or strap fastener, shoe, L. F. Ramsey.. 775,466



"Star" Foot and Power Screw Cutting Automatic Cross Feed Lathes

FOR FINE, ACCURATE WORK

Send for Catalogue B.

SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N.Y., U.S.A.

ENGINE & FOOT LATHES. MACHINE SHOP OUTFITS. TOOLS AND SUPPLIES. CATALOGUE FREE. SEBASTIAN LATHE CO. 120 CULVERT ST. CINCINNATI, O.

Foot and Power and Turret Lathes, Planers, Shapers, and Drill Presses.
SHEPARD LATHE CO., 133 W. 2d St. Cincinnati, O.

FRENCH—GERMAN
SPANISH—ITALIAN

Spoken, Taught and Mastered Through the

LANGUAGE PHONE-METHOD

Combined with

The Rosenthal Common Sense Method of Practical Linguistry

The Latest and Best Work of Dr. Richard S. Rosenthal
YOU HEAR THE EXACT PRONUNCIATION OF EACH WORD AND PHRASE. A few minutes' practice several times a day at spare moments gives a thorough mastery of conversational French, German, Spanish, or Italian.

Send for testimonials, booklet, and letter.

International Language-Phone Method,
1101-C, Metropolis Bldg., Broadway and 16th St., N.Y.



WATER A PERPETUAL SUPPLY *usually* means perpetual expense. The windmill and gasoline engine are costly to install and run. **Niagara Hydraulic Ram** will work continuously wherever there is a running stream. Nothing to blow down, blow up, or require attention. Requires less head of water to operate than any other ram. *Never needs repairs.* Catalogue free.

Niagara Hydraulic Engine Co.,
CHESTER, PA.

MEDART
Boat Building Materials

make possible the construction of high-class boats by amateurs at a small cost. Send stamp for catalog.

FRED MEDART
3545 DeKalb Street, St. Louis, Mo.

BRASS OR STEEL

THE CLIPPER CLIP

Its triangular shape prevents entangling and gives three times the capacity of any other Clip for attaching papers together.
Best & Cheapest. All Stationers.

CLIPPER MFG. CO.,
401 West 124th St., New York, U.S.A.
For free samples and information write to us.

Kerosene Oil Engine

Nothing but Kerosene Oil to run it

Simple, Safe and Efficient. Needs little attention, is less likely to get out of order, and is cheaper to run than any other engine manufactured. **Economical and Easily Operated.**

International Power Vehicle Co.
Stamford, Conn.

TAKE THE NICKEL PLATE ROAD FOR THE ST. LOUIS FAIR.

Lowest Rates and many unusual privileges. Special $15.00 rate on certain dates. Full information on application to local Agents, or R. E. Payne, General Agent, 291 Main St., Buffalo, N. Y., or A. W. Ecclestone, D.P.A., 385 Broadway, New York.



DO YOU USE GRINDSTONES?

If so we can supply you. All sizes **mounted and unmounted**, always kept in stock. Remember, we make a specialty of selecting stones for all special purposes. *Ask for catalogue*

The CLEVELAND STONE CO.
2d Floor, Wilshire, Cleveland, O.

MACHINE No. 78.
Range 2½-4 in. R. H.

For Either Hand or Power

This machine is the regular hand machine supplied with a power base, pinion, countershaft, etc., and can be worked as an ordinary power machine or taken from its base for use as a hand machine. Length of pipe handled easily in small room. Illustrated catalogue —price list free on application.

THE CURTIS & CURTIS CO.,
6 Garden St., BRIDGEPORT, CONN.

JUST PUBLISHED

American Estates and Gardens

4to. 11x13½ inches. Illuminated Cover and 275 Illustrations. 340 Pages. Price, $10.00

By BARR FERREE

Editor of Scientific American Building Monthly, Corresponding Member of the American Institute of Architects and of the Royal Institute of British Architects



A SUMPTUOUS book dealing with some of the most stately houses and charming gardens in America. The illustrations are in nearly all cases made from original photographs, and are beautifully printed on double coated paper. Attractively bound. This book will prove one of the most salable holiday books of the season, and will fill the wants of those who desire to purchase a luxurious book on our American homes. An illustrated prospectus mailed free on request.

MUNN & COMPANY
Subscription Dept. O.O.

Publishers of "Scientific American"

337 Broadway, New York

Ladder elevator, self supporting and extension, E. Maxey 775,373
Ladder, portable, M. Tetzlaff 775,488
Lamp base, incandescent, A. Swan 775,689
Lamp, electric arc, T. L. Carbone 775,442
Lamp, miner's safety, R. C. Simpson 775,782
Lamp or gas light holder, movable incandescent, J. H. Stanton 775,504
Lamp socket, plural, R. B. Benjamin, reissue 12,286
Lamps, rosette for suspending or supporting incandescent, H. E. Rossiter 775,779
Land roller and harrow, combined, J. H. Massmann 775,575
Latch, door, R. F. Pinegar 775,854
Lathe, automatic, L. T. Kline 775,302
Leather, treating, P. Magnus 775,839
Lens combination for producing virtual images, M. von Rohr 775,353
Letter box, J. N. Nutt 775,543
Level, adjustable, G. H. Whitehouse 775,483
Limb, artificial, L. A. Weisser 775,506
Liquids, heating, A. Waldbaur 775,788
Logging sled draft mechanism, H. B. Frey. 775,900
Loom, W. F. Draper 775,558
Loom, J. H. Cobb 775,895
Loom, E. S. Draper 775,898
Loom, lappet, J. C. Brooks 775,893
Loom lay downhold, E. S. Wood 775,881
Loom let-off mechanism, J. T. Meats 775,336
Loom picker stick motion, G. Boisvert 775,890
Loom shuttle, Gregory & Brown 775,420
Loom shuttle, check, F. Ott 775,308
Loom shuttle locking means, M. L. Stone.. 775,868
Loom temple, A. Meunier 775,775
Loom warp stop-motion, J. T. Meats 775,452
Machine element, C. D. Rice 775,735
Mail bag deliverer, W. D. Briggs 775,517
Mail box, J. H. Knope 775,404
Mail box, etc., M. B. & H. S. Mills..... 775,630
Mandrel, expanding lathe, G. R. Rich 775,579
Mandrels, machine for grooving wire, M. Stadler 775,613
Manicure implement, F. B. La May 775,568
Mat, Norton & Knauff 775,633
Match scratching device, B. C. Cole 775,296
Metallic fabric, E. A. Bedient 775,620
Metals from their ores, extracting, F. H. Long 775,405
Microteme, C. F. Dieckmann 775,556
Milk can lid or cover, J. J. Snigo 775,687
Milk receptacle lock, W. Goodchild 775,397
Milking device, V. O. Johnson 775,726
Mixer, G. Thom 775,710
Moistener, envelop, W. Holt 775,289
Molding apparatus, C. P. Melvin 775,374
Molding machine, F. W. Hall 775,530
Molding machine, centrifugal, J. C. F. Lafeuille 775,371
Mop or wiper, H. O. Thomas 775,463
Mortising machine, D. W. Cole 775,745
Motor case and gear, L. S. Pfouts 775,311
Motor frame, T. C. Dunlap 775,446
Motor vaporizer, hydrocarbon, A. Wassmann 775,321
Music leaf turner, I. J. Clarke 775,799
Musical instrument, H. J. Isbell 775,658
Musical instrument, F. O. Gutman 775,817
Musical instrument devices, automatic spring winding mechanism for mechanical, Sharps & Cooper, reissue 12,289
Musical instrument tremolo attachment, J. A. Burchit 775,327
Nail blanks, machine for swaging heads on, E. Perkins 775,499
Naval architecture, G. F. R. Blochmann.. 775,889
Nut, etc., mold, Bone & Reid 775,795
Oil burner, R. Meldrum 775,428
Oil burner, A. J. O'Brien 775,762
Oil burner, blue flame, W. R. Jeavons 775,903
Oil can, J. E. Albers 775,324
Oleo resin from the peel of citrus fruits, extracting, E. J. Sheehan 775,502
Oleo resinous product from citrus fruits, E. J. Sheehan 775,546
Ordnance, W. H. Bevans 775,793
Oscillating motor, T. M. Foote 775,560
Paper making apparatus, R. Binns 775,511
Paper pulp, production of, I. Kitsee 775,829
Paper shaping machine, C. H. Dunning 775,330
Paper trimming or cutting tool, H. S. Williams 775,434
Paving block or set for use along tramway rails, J. G. Wolf 775,486
Pen, fountain, A. R. Leib 775,907
Penholder, W. H. Reed 775,734
Pencil, J. D. R. Lamson 775,493
Pencil, lead, A. P. Jacob 775,423
Pencil sharpener, F. P. Lovejoy 775,707
Phenol compound, C. Gentsch 775,814
Phonograph repeating attachment, E. L. Aiken 775,591
Photographic printing frame, Smith & Hauer 775,785
Photographic printing frame support, J. S. Cummings 775,555
Photographic shutter, J. S. Wright 775,436
Pick, miner's, W. Ashert 775,325
Picker sticks, adjustable back-stop for, O. Benson 775,886
Pictures, producing invisible, E. Doberenz.. 775,747
Pipe covering and making same, J. A. McConnell 775,537, 775,541
Pipe coverings, apparatus for molding, J. A. McConnell 775,540
Pipe expanding and flanging machine, metal, L. D. Lovekin 775,574
Pipe finishing tool, flanged, L. D. Lovekin. 775,572
Pipe threader, D. Edwins 775,721
Pipe wrench and cutter, double acting, G. E. R. Rothenbucher..... 775,581
Plane, J. Muehl 775,378
Plastic composition, R. McCarrel 775,631
Plastic material molding apparatus, J. A. McConnell 775,542
Plate or saucer holder, J. E. Twitchell.... 775,874
Plowshare sharpener, L. J. Cox..... 775,346
Plowshares, manufacture of landsides for, J. B. Jarmin 775,424
Powder charger, Lippart & Warren..... 775,629
Power transmitting and reversing mechanism, R. Symmonds 775,409
Precious metal from ores, apparatus for extracting, J. J. Berrigan 775,414
Precious metal from ores, extracting, J. J. Berrigan 775,509
Precious stones, apparatus for cutting and polishing, F. R. Kneip 775,567
Press or machine for making saggers, etc., E. W. Leigh 775,706
Printing press sheet delivery apparatus, cylinder, W. S. Huson 775,657
Pruning hook, C. Gregory 775,649
Puller. See Spike puller.
Pulp beating machine, L. A. Thomas..... 775,873
Pulp mills, neutralizing liquids effluent from wood, C. W. Doughty 775,525
Pulp web and spool, R. Binns 775,513
Pump, air, G. L. Bennett 775,885
Pump governor, R. Conrader 775,391
Punch, ticket, C. W. Kuen 775,303
Punching bag apparatus, C. F. Held..... 775,653
Puzzle, E. L. Young 775,685
Pyrotechnical compound, K. Hufnagel .. 775,822
Radiator and ventilator, heat, J. J. Kulage 775,333
Rail fastener, guard, D. F. Vaughan.... 775,738
Rail joint, A. L. Stanford 775,386
Rail joint, M. Barschall 775,643
Rail joint, W. E. Palmer..... 775,852
Railway, coasting or gravity, G. A. De Baun 775,702
Railway crossing, W. J. Bazarek 775,551
Railway signal system, automatic, J. W. Shattuck 775,479
Railway signaling apparatus, J. T. Cade. 775,797
Railway signaling, electric circuits and apparatus for, H. W. Spang..... 775,461
Railway signaling system, electric, Sera & Stolfi 775,736
Railway switch, S. F. Kates 775,904
Railway switch, elevated, J. Hughes..... 775,300
Railway tie, F. W. Mettler 775,454
Railway tie, A. A. Kappenhagen..... 775,473
Railway tie, C. J. Swink 775,480
Railway track switch, electrically operated, G. H. Fretts 775,529
Range boilers, gas heating attachment for, H. G. Schramm 775,781
Ratchet mechanism, C. F. Dieckmann... 775,557
Razor, safety, A. Muller..... 775,379
Reflector, E. L. Zalinski 775,741
Refrigerating machines, absorber for ammonia absorption, R. J. Cracknell.... 775,896

IT'S SUMMER NOW IN

JAMAICA

HAMBURG-AMERICAN LINE

For the Winter

GO TO

JAMAICA

BY THE STEAMERS OF THE

ATLAS LINE SERVICE

WEEKLY SAILINGS TO

JAMAICA, COLOMBIA, COSTA RICA, and NICARAGUA; also to HAYTI

To Jamaica, $40; round trip, $75. Twenty-Three Day Cruise, $125. Rates include stateroom accommodation and meals. For particulars apply

HAMBURG-AMERICAN LINE

35-37 Broadway, N. Y.
159 Randolph Street, Chicago
1229 Walnut Street, Phila.
901 Olive Street, St. Louis.

Good Pencils

Dixon's Pencils —some for one purpose—some for another. One just for yours.

Dixon's Pencil Guide, a 32-page book, **indexed by vocations,** correctly indicates the right pencil for your use. Sent *free.*

Department W,
JOSEPH DIXON CRUCIBLE CO.
Jersey City, N. J.

KLIP-KLIP

THE POCKET MANICURE

COSTS 25 CENTS LASTS 25 YEARS

Solid German Silver. Trims, Files and Cleans the nails with either hand. Don't take imitations. Sold everywhere or by mail for 25c. Money back if you want it. Manicure Book, "A Handy Hand Book of the Hands"—complete instruction on the care of the hands and nails. Sent for two 2c. stamps.

Klip-Klip Co., 556 Clinton Ave. S., Rochester, N. Y.

A. W. FABER

Manufactory Established 1761.

LEAD PENCILS, COLORED PENCILS, SLATE PENCILS, WRITING SLATES, INKS, STATIONERS RUBBER GOODS, RULERS, ARTISTS' COLORS.

78 Reade Street, New York, N. Y.

GRAND PRIZE, Highest Award, PARIS, 1900.

HOW FAR DO YOU WALK IN A DAY?

Did it ever occur to you that perhaps you walked miles just going around your home, shop or office? Perhaps you'd like to know. If so, get a Pedometer. A Pedometer is an ingenious affair that goes when you go and stops when you stop. This instrument has heretofore cost from ten to fifteen dollars. It is not a toy, but an accurate and valuable recorder of distances.

YOU CAN GET A PEDOMETER FREE!

by sending us $1.00 for a year's subscription to MODERN MACHINERY, our monthly magazine, which will keep you posted on the great progress which is being made in the machinery world (and if you would keep abreast of the times you must read MODERN MACHINERY), interestingly written, well illustrated. Sample Copy, 10c; $1.00 per year—and a Pedometer, FREE. Subscribe Now.

MODERN MACHINERY COMPANY.
813 Security Building, CHICAGO, ILLINOIS

ARTESIAN

Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 3000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1200 feet. Write us stating exactly what is required and send for illustrated catalogue. Address

PIERCE WELL ENGINEERING AND SUPPLY CO.
2 128 LIBERTY STREET, NEW YORK, U. S. A.

Regulator, R. Conrader	775,392
Relay, resonance, P. O. Pedersen	775,680
Retort, S. L. Hague	775,448
Rivet, G. L. Miller	775,728
Rivet, bolt, etc., mold, Bone & Reid	775,794
Rocking horse, traveling, A. Hettel	775,725
Rod bending machine, W. J. Kurtz	775,774
Roller mill feed mechanism, J. J. Gerard	775,350
Roofing or flooring, flexible, Rugen & Abraham	775,635
Roost, poultry, F. C. Jahnke	775,603
Rotary engine, V. Behringer	775,413
Rotary engine, J. W. Pickel	775,429
Rotary engine, F. F. Norden	775,632
Rotary motor, A. A. Ewald	775,297
Safe or vault, S. L. Smith	775,356
Sandal, B. R. Bonney	775,440
Sash fastener, J. H. Clements	775,744
Sash fastener and lift, W. W. Bauman	775,593
Sash lock, C. Hearnshaw	775,602
Sash lock, window, J. C. Beggim	775,524
Sash, window, C. M. Rhodes	775,858
Saw carriage for cutting bevel boards, A. W. Tait	775,787
Saw guide, gang, C. A. Norlin	775,477
Sawmill, R. L. Neubert	775,576
Scoop, measuring, F. S. Bishop	775,326
Screw holder and driver, C. Lusted, Sr	775,427
Seal, bottle, W. E. Heath 775,651,	775,652
Seed cleaning machine, vegetable, J. B. Green	775,675
Separators, discharge regulating device for, J. J. Berrigan	775,510
Sewer cleaning machine, P. J. Healey	775,677
Sewing machine buttonhole cutter, A. Jeude	775,565
Sewing machine shuttle, H. A. Dodge	775,362
Sewing machine thread clamp, wax thread, H. A. Dodge	775,363
Shade and curtain holder, combined, J. O. Kridelbaugh	775,474
Shaft coupling, C. A. Backstrom	775,884
Shaft with changeable speed, counter, G. Langen	775,372
Shaping machine, Potter & Johnston, reissue	12,287
Sheet delivery, A. K. Taylor	775,319
Shelf, library, N. B. Parsons	775,496
Shelf, library, N. B. Parsons, et al	775,498
Ship's signal, F. W. Wood	775,507
Shoulder strap holder, R. Morris	775,845
Shrapnel, P. D. Van Essen	775,640
Shuttle, J. E. Welton	775,589
Shuttle, self-threading, W. L. Hall	775,676
Sifter, ash, W. T. Whiteway	775,590
Sign, R. W. Clark	775,295
Sign, display, R. W. Clark	775,294
Signal. See Ship's signal.	
Signaling apparatus, electrical, S. Cabot	775,390
Skirt and undergarment adjuster and hose supporter, combined, F. E. Moody	775,305
Skiving machine, band knife, G. O. Jenkins	775,564
Slicer for bread, etc., I. Goldstein	775,601
Sluice box, rotary, J. L. Porter	775,578
Snap, harness, J. W. Lawhead	775,678
Snow plow, E. Bowman	775,293
Spark gap, rotary, F. F. Strong	775,872
Speed and reversing mechanism, variable, F. O. Farwell	775,647
Spike puller, H. Q. Hood	775,534
Spindles, bobbin clutching means for rotatable, W. E. Allen	775,883
Spindles, bobbin retaining means for rotatable, F. E. Norcross	775,850
Spinning machine, Alexander & Napier	775,549
Spinning spindle, J. E. Prest	775,681
Spool rolling and finishing apparatus, R. Binns	775,514
Spray bath, Burger & Williams	775,796
Spring end plate, J. Carroll	775,554
Spring wheel, E. Einfeldt	775,806
Stack construction, N. B. Parsons	775,497
Stack cover, hay, C. B. Thummel	775,505
Stamp mill tappet, W. E. Ingram	775,625
Stay, coat, F. C. Klipstein	775,628
Steam engine, F. Egge	775,527
Steam engine, A. Langlais	775,605
Stereoscopic printing device, F. A. Brownell	775,552
Stocking supporter, C. J. Higley	775,422
Stone or other material, means and apparatus for use in cutting or dressing or polishing, F. M. McLarty	775,455
Stove, gas burning fireplace, H. A. S. Howarth	775,656
Strainer, jelly, A. H. Williams	775,716
Street sweeper, A. Larson	775,569
Stretcher, R. C. Smith	775,737
Surgical cushions, etc., cap for air valves for, C. W. Meinecke	775,841
Suspenders, W. Freeman	775,749
Swinging gate, D. H. Iseminger	775,772
Switch operating device, H. M. Cosey	775,599
Switch point locking mechanism, Maher & Harbison	775,840
Table, W. H. Gibbes	775,724
Tack puller, J. M. Ranck, Sr	775,856
Tap for barrels, casks, etc., R. H. Salmons	775,609
Tap or thread cutter, T. Dollard	775,672
Targets, apparatus for signaling the value of shots on, T. Murray	775,761
Telegraph pole, W. Schutz	775,637
Telegraph, wireless, R. L. de Moura	775,846
Telephone system, G. M. Crockett	775,521
Telephone, wireless, R. L. de Moura	775,337
Theater chair, Wiersching & Bergstrom	775,879
Thill coupling, G. E. Clow	775,444
Threshing and cleaning apparatus, seed cotton, H. H. Kelly	775,754
Ticket, railway, Lyon & Donaldson	775,838
Tide and wave motor, G. W. Hazel	775,421
Tile construction, illuminating, P. H. Jackson	775,626
Time lock, H. M. Dalton	775,523
Time of employees, machine for keeping the, T. Dow	775,348
Tire for vehicle wheels, pneumatic, Karreman & Del Guerra	775,492
Tire friction tread, vehicle, L. P. Faison	775,722
Tire, pneumatic, F. R. Keith	775,824
Tire, rubber, J. F. Byers	775,361
Tobacco pipe, C. H. Rideout	775,407
Tobacco pipe, W. K. Horn	775,624
Tongue support, M. S. Evans	775,811
Trace carrier, harness, J. Hebel	775,400
Traction increasing device, R. C. Lowry, 775,836,	775,837
Traction wheel, E. Einfeldt	775,805
Traveling bag, case, etc., C. H. Anderson	775,343
Trellis, vine, J. Seelhorst, Jr	775,683
Trolley, Naret & Ernst	775,777
Trolley, Elker & Tobin	775,808
Trolley, W. S. Stockton	775,867
Trolley, overhead, J. G. Johnston	775,627
Trolley pole, W. E. Harmon	775,531
Trolley wheel, M. L. Mowry	775,847
Truck bolster, car, G. G. Floyd	775,559
Trunk and desk, combined, T. McCabe, Jr	775,731
Truss, cardiac, E. Abee	775,342
Tube or spool making apparatus, R. Binns	775,512
Tubes, pipes, etc., apparatus for cleaning, F. Nowotny	775,679
Tuning hammer, W. H. Porter	775,383
Tuning peg, stringed instrument, F. W. Becker	775,767
Turbine, C. N. Schottmuller	775,315
Turbine, C. A. Parsons	775,634
Type distributing apparatus, L. K. Johnson	775,426
Typewriter cylinder scale, O. C. Kavle	775,332
Typewriters, etc., mechanism for locking the key levers of, W. F. Helmond	775,331
Typewriting machine, E. B. Cram	775,394
Typewriting machine, J. D. White	775,739
Typewriting machine, G. M. Kitzmiller	775,830
Valve, air relief, J. T. Lewis	775,661
Valve mechanism, Thomson & Ball	775,586
Valve mechanism for controlling flow of liquids, A. Priestman	775,855
Valve operating device for blowing engines, electrical, S. T. Wellman	775,878
Valve, regulating, J. Johnson	775,823
Variable speed motor, M. Pfatischer	775,310
Vault, Given & Hollar	775,674
Vegetable cutter, J. Valk	775,639
Vehicle body corner, W. B. C. Hershey	775,449
Vehicle brake, automatic, C. A. Harris	775,298
Vehicle, traction, A. S. Kaplan	775,403
Vehicle train, C. Renard	775,765
Vehicle wheel, W. B. Keighley	775,753
Vehicle wheel, J. Lefler	775,831

THE IDEAL SIGHT RESTORER

RESTORES THE SIGHT
WEAK EYES MADE STRONG.
SPECTACLES ARE A NUISANCE, NECESSITY ONLY MAKES ONE WEAR THEM.

PREVENTS FAILING SIGHT
DULL EYES MADE BRIGHT.
Write for ILLUSTRATED TREATISE ON THE EYE, Mailed Free.
THE IDEAL COMPANY, 239 BROADWAY, NEW YORK.

A MARVELOUS DISCOVERY

FREE to the world, beginning in the January issue of Physical Culture magazine. A wonderful method for strengthening the vital organs, Heart, Lungs, Stomach, Intestines, Kidneys, etc. Not a series of exercises, but a simple home method that produces immediate results. Wonderfully useful to either man or woman, invalid or athlete. All physical complaints, simple or serious, are caused by functional disorder of the vital organs. Strengthen these organs and the disease disappears. A series of articles explaining this secret method begins in the January issue of our magazine; 100 pages; 100 illustrations. For sale at all news stands. If your newsdealer doesn't keep it, send his name and we will send free copy for you in his care, or send us $1.00 for a year's subscription. Money returned if not satisfied.
PHYSICAL CULTURE PUBLISHING COMPANY, NEW YORK CITY



There and Back
WHAT A RELIEF
Write us to-day for information
GRANT-FERRIS CO
Troy, N. Y.

THE EUREKA CLIP

The most useful article ever invented for the purpose. Indispensable to Lawyers, Editors, Students, Bankers, Insurance Companies and business men generally. Book marker and paper clip. Does not mutilate the paper. Can be used repeatedly. In boxes of 100 for 25c. To be had of all booksellers, stationers and notion dealers, or by mail on receipt of price. Sample card, by mail, free. Manufactured by Consolidated Safety Pin Co., Box 121, Bloomfield, N. J.



Size No. 2

THE BEST COOKING RANGE MADE

Sold for Cash or on Monthly Payments
$10 to $20 Saved
Freight Paid
Your money refunded after six months' trial if
Clapp's Ideal Steel Range

is not 50 per cent. better than others. My superior location on Lake Erie, where iron, steel, coal, freights and skilled labor are cheaper and best, enables me to furnish a TOP NOTCH Steel Range at a clean saving of $10 to $20. Send for free catalogues of five distinct lines, 50 styles and sizes, with or without reservoir, for city, town or country use.

CHESTER O. CLAPP, 688 Summit St., Toledo, Ohio
(Practical Steel Range Man)

Every Mechanic Should Own It.

Montgomery & Co.'s Tool Catalogue

which is thoroughly up-to-date. 704 pages and discount sheet. Sent by mail for 25 cents.

MONTGOMERY & CO.,
105 Fulton St., New York City.



BARKER MOTORS

Have more good points, fewer parts and require less attention in operation than any other.

Launches, Valves, Specialties.

C. L. Barker, Norwalk, Ct.

THE PANAMA CANAL IS DESCRIBED from the engineering standpoint in SCIENTIFIC AMERICAN SUPPLEMENT 1359. Price 10 cents, by mail. Munn & Company, 361 Broadway, New York City, and all newsdealers.

The Brennan Motor

IS GUARANTEED

14 H. P. develops rated power at 700 R. P. M., develops 16 H. P. at 800, and 18 H. P. at 900. Motors are used for automobile, marine and stationary purposes. They are sure and quick to run.

BRENNAN MOTOR CO. - Syracuse, N. Y.

A MONEY MAKER

Hollow Concrete Building Blocks. Best, Fastest, Simplest, Cheapest Machine.

PETTYJOHN BROS.
1315 N. 1st Street, Terre Haute, Ind.

The Apple

For Gas Engines, Launches, Automobiles, etc.

No more belt, battery and commutator troubles. Dirt and waterproof. Easily attached, increases power and speed. Send for full particulars on our storage batteries, spark coils, timing devices, spark plugs, and all kinds of ignition apparatus.



The Dayton Electrical Mfg. Co.
88 Reibold Bldg., Dayton, Ohio.

Squabs Pay Beat Hens

Easier, need attention only part of time, bring big prices. Raised in one month. Attractive for poultrymen, farmers, women. Send for FREE BOOKLET and learn this *immensely rich home industry.*

PLYMOUTH ROCK SQUAB CO., 289 Atlantic Ave., Boston, Mass.

WATER MOTOR Indispensable for Home and General Use

For sharpening edge tools, such as knives, scissors, hatchets, etc. For cleaning and polishing metals, silverware, glassware, and furnishing light power for mechanical purposes. Dentists, butchers, cooks, jewelers, carpenters, plumbers automobilists and mechanics generally cannot afford to be without this newly patented invention. Price $3.00, complete, including emery wheel, buffing wheel and pulley. Sent upon receipt of this amount, or C. O. D. if preferred. Money refunded if not satisfactory. This is not a toy. Booklet giving full description sent free. Correspondence with dealers is solicited, and agents wanted everywhere.

WARNER MOTOR CO., Dept. 15
P. O. Box 4, Station G, New York City

Induction Coils



for X-Ray Apparatus and for Wireless Telegraphy. Special Jump Spark Coil for Automobiles and Gas Engines.

E. S. RITCHIE & SONS, Brookline, Mass.

KENT POCKET METERS

Automatic Volt-Ammeter



Is designed and calibrated especially for testing batteries on gasoline automobiles and launches and for any other use of like capacity. Accurate and substantial. Ampere reading made simply by pressing button. The most convenient and complete battery tester on the market.

Volt-Ammeter $6.00. Amperemeter $5.00.
Atwater Kent Mfg. Works, 110 N. 4th St., Philadelphia, Pa

If You Want the Best Lathe and Drill CHUCKS

BUY WESTCOTT'S *Strongest Grip, Greatest Capacity and Durability, Cheap and Accurate.*



Westcott Chuck Co., Oneida, N. Y., U. S. A.
Ask for catalogue in English, French, Spanish or German.
FIRST PRIZE AT COLUMBIAN EXPOSITION, 1893.

MAXIMUM POWER—MINIMUM COST



If you use a pump for beer, lard, acids, starch, petroleum, brewer's mash, tanner's liquor, cottonseed oil or fluids, hot or cold, thick or thin you want to get the TABER ROTARY PUMP which does the most work at the least expense. Simply constructed. Can be run at any desired speed. Perfectly durable. All parts are interchangeable. Needs no skilled workman. Defects guaranteed. *Catalogue free.*
TABER PUMP CO., 32 Wells St., Buffalo, N. Y., U. S. A.

PRACTICAL ARTICLES ON

EXPERIMENTAL ELECTRO-CHEMISTRY

By N. MONROE HOPKINS, Ph.D.
Assistant Professor of Chemistry in the George Washington University, Washington, D. C.

are appearing in the

Scientific American Supplement

The articles describe simply and clearly experiments in electro-chemistry with easily constructed apparatus. Intelligible and lucid drawings and photographs accompany the articles. The entire series, when complete, will constitute a splendid student's manual of electro-chemistry.
Each number of the SUPPLEMENT costs 10 cents by mail. Subscribe for the year and be sure to receive all the papers containing the articles.

MUNN & COMPANY 361 Broadway NEW YORK

EVERYBODY

Is interested in Stocks or Bonds listed on the various stock exchanges, either as an investor or an operator.

Our Weekly Market Letter

will be found invaluable. Your name on our mailing list insures your receiving it every week.

Corey, Milliken & Co.
BANKERS AND BROKERS
15 State Street Boston, Mass.

The HOW and WHY of Electricity
By CHARLES TRIPLER CHILD

A book that all may read with understanding. The story of electricity stripped of formulæ and written for those who wish to learn. **Price $1,** postage prepaid.

New York *Sun:* "We know nothing that gives so much real help in so short a space."

Published by **ELECTRICAL REVIEW PUB. CO.**
13 Park Row, New York

Sample copy of the Electrical Review FREE, if requested

THOUSANDS are successful and earning better positions and salaries studying **Electrical Engineering, Steam Engineering, Mechanical Engineering, Mechanical Drawing, Electric Motorman's Course, Dynamo Tender's Course, Telegraphy, Short Electrical Course, Arithmetic, Algebra, by mail.** Thomas A. Edison endorses Institute. Text books free. Students helped to positions. Write for free book, "Can I Become An Electrical Engineer?"
ELECTRICAL ENGINEER INSTITUTE
Dept. A, 240 West 23d St., New York

Spangenberg's Steam & Electrical Engineering

Price $3.50

By E. SPANGENBERG, M.E formerly Superintendent St. Louis School of Engineering, ALBERT UHL, A.I.E.E., and E. W. PRATT. 672 pages, 648 illustrations. Only work containing 1035 Questions and Answers on every branch of engineering.

Easy to Understand

Written by practical men for practical men in an easy and simple style. Treats of **Gas and Gasoline Engines,** Stationary and Locomotive Engineering, Compressed Air, Refrigeration, Hydraulic Elevators, and has **Over 200 Pages on Electricity.** Agents wanted everywhere.

GEO. A. ZELLER, Publisher, 68 S. 4th St., St. Louis, Mo.
40-page pamphlet tells all about it.



FOR GUNSMITHS, TOOL MAKERS, EXPERIMENTA L & REPAIR WORK, ETC.

From 9-in. to 13-in. swing. Arranged for Steam or Foot Power, Velocipede or Stand-up Treadle. *Send for Lathe Catalog.*

W. F. & JNO. BARNES CO.
Established 1872.
1999 Ruby St., ROCKFORD, ILL.

Bright as Sunlight

Brighter than gas or electricity, and cost less than kerosene. No smoke, no dirt, no smell. Save money and have better light by writing now for our special introductory offer. Any of our lamps sent on trial—satisfaction guaranteed. Our agents make $200 to $300 a month. Write today for catalog, prices and special proposition. We also make complete systems for houses and stores.

The Ann Arbor Gasoline Lamps & Systems

Superior Mfg. Company
255 Second St. Ann Arbor, Mich.

To Owners of Gasoline Engines, Automobiles, Launches, Etc

The Auto-Sparker

does away entirely with all starting and running batteries, their annoyance and expense. No belt—no switch—no batteries. Can be attached to any engine now using batteries. Fully guaranteed; write for descriptive catalog.

Motsinger Device Mfg. Co.,
14 Main St., Pendleton, Ind.

50 Years' Experience

PATENTS

Trade Marks, Designs, Copyrights, Etc.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents.

Patents taken through MUNN & Co. receive *Special Notice,* without charge, in the

Scientific American

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, $3 a year; four months, $1. Sold by all newsdealers.

MUNN & CO. 361 Broadway, **New York**
Branch Office 625 F St. Washington, D. C.

Ventilators. See Window ventilator.
Vermin trap, G. Andrus 775,292
Vessels, apparatus for raising sunken, M. Lacey 775,370
Violin chin and shoulder rest combined, F. W. Becker 775,792
Violin chin rest, F. W. Becker 775,465
Wagon frame, metallic, E. Einfeldt 775,807
Wagon reach, J. Simpson 775,316
Water elevating apparatus, A. Sundh..... 775,585
Water hoisting apparatus, W. H. Moody.. 775,843
Water motor, J. F. Myser 775,776
Water purifier and elevator, J. W. Carpenter 775,443
Water purifying apparatus, J. C. W. Greth 775,901
Water tube boiler, H. L. Wilson..... 775,435
Welding or forging metallic rings or links, machine for, J. Girlot 775,815
Well jack, W. E. A. Pipher 775,733
Well sinking apparatus, M. T. Chapman.. 775,417
Wheels, cranks, etc., fastening for, J. V. Pugh 775,764
Whip, drover's, H. Brown 775,669
Wind motor, A. Wedrick 775,877
Window, W. B. Culver 775,522
Window, A. G. Steinbrenner 775,866
Window closer, automatic, H. C. Smith... 775,547
Window frame and sash, metallic, J. Bogenberger 775,668
Window ventilator, A. U. Chase 775,798
Wire cutter and pliers, combined, J. W. Calhoun 775,699
Wire stretcher, P. Epperson 775,469
Wire weaving loom, R. H. Bliss 775,888
Wrench. See Pipe wrench.
Wrench, F. Hachmann 775,398
Wrench, L. W. Siple 775,783
Zinc, apparatus for the extraction of, C. S. Brand 775,359, 775,360

DESIGNS.

Badge, G. L. Gillespie 37,236
Badge or similar article, H. L. Lang..... 37,237
Bottle top, pepper or salt, C. V. Helmschnied 37,243
Candelabrum, S. W. Babbitt 37,245
Jewel casket or similar article, E. L. Brainard 37,238
Lamp shade, electric, H. D'Olier, Jr..... 37,246
Oven plate, J. Magee 37,248
Pipe, W. B. Porter 37,244
Shears, W. F. Hobbs 37,242
Spoon, fork, or similar article, Margolis & Metzger 37,241
Spoon or similar article, W. C. Codman.. 37,240
Spoons, forks, or similar articles, handle for, W. C. Codman 37,239
Stove plates or similar articles, rim for, J. Magee 37,247
Trimming, A. M. Weber 37,249

TRADE MARKS.

Agricultural machines and extra and repair parts and pieces therefor, certain named, International Harvester Co. of America 43,742
Bells, artificial and ornamental. L. Wertheimber 43,739
Belts and buckles therefor, E. & J. Bass.. 43,747
Cigars and cigarettes made from cigar tobacco, Victor Talking Machine Co.... 43,733
Coats, vests, trousers, overcoats, and raincoats, Rosenwald & Weil..... 43,725
Custard, Bunham Manufacturing Co..... 43,750
Deodorizing toilet preparations, Udor Manufacturing Co. 43,732
Drinks, non-alcoholic fruit, F. Hartmann, 43,736, 43,737
Fabrics, linen, Syndicate Trading Co..... 43,743
Fabrics, upholstery textile, Philadelphia Tapestry Mills 43,744
Fireproof garments, Textile Fireproofing Co. 43,748
Glass, window, Pittsburg Window Glass Co. 43,740
Hose, boys' ribbed, York Knitting Mills Co. 43,728
Hose, misses' ribbed, York Knitting Mills Co. 43,729
Knit undergarments, certain named, B. Lodge & Co. 43,727
Measuring tapes, Keuffel & Esser Co., 43,745, 43,746
Medical compounds, certain named, H. S. Wellcome 43,738
Medical compounds, certain named, Parker & Budd 43,753
Medicine for certain named diseases, Maize Products Co. 43,752
Medicine for the cure of diseases of the feet, E. C. Rice 43,754
Mills for grinding grain, seeds, and drugs, New Winona Manufacturing Co..... 43,755
Muffins, Ives Company 43,751
Puzzles, Blackburn, Hough & Co..... 43,722
Shirts, S. Liebovitz Sons 43,726
Shoes, leather, Peters Shoe Co..... 43,723
Snap fasteners, United States Fastener Co., 43,730, 43,731
Syrups, saccharine, Wogan Bros. 43,749
Tea, Berry Dodge & Co..... 43,734, 43,735
Tires, rubber, Jewell Belting Co. 43,741
Woolen piece goods, A. D. Ellis 43,724

LABELS.

"Anti-Itisine," for surgical dressing, C. L. Boyd 11,612
"Batnette for Lawn or Parlor." for a game, J. C. Tanty 11,617
"Batnette, The Newest Game." for a game, J. C. Tanty 11,618
"Ben Hur," for soap, Cape City Soap Works 11,615
"Big Cape," for soap, Cape City Soap Works 11,616
"C. Maspero's Medicinal Olive Oil," for olive oil, C. Maspero..... 11,609
"Germicide Dandruff Cure," for dandruff cure, A. Burrows 11,611
"Magnolia Syrup," for syrup, Magnolia Syrup Co. 11,606
"Merry War," for soap, Cape City Soap Works 11,614
"Nitro Powder Solvent No. 9," for a cleaning compound, F. A. Hoppe 11,613
"Old Tennessee Club," for whisky, S. S. Price 11,605
"Rosia Skin Food," for skin food, M. Williams 11,610
"S. B. Clark's Nicest Biscuit, New York," for biscuits, S. B. Clark 11,608
"Silver Slipper Chop," for tea, P. Baumgarten 11,604
"Sunny Side Pork and Beans," for pork and beans, Tip Top Ketchup Co. 11,607

PRINTS.

"At Hearts—Wish I could give you my heart," for playing cards, United States Playing Card Co. 1,150
"Budweiser Girl," for beer, Anheuser-Busch Brewing Ass'n 1,145
"Colgan's Taffy-Tolu Chewing Gum," for chewing gum, Colgan Gum Co. 1,147
"Men's Apparel," for men's apparel, W. C. Both 1,149
"Sparrow's Chocolates," for candy, H. F. Sparrow Co. 1,146
"'Walk-off' Clothes," for clothes, Walcoff, Udell & Co. 1,148

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

THE HARRINGTON & KING PERFORATING CO.
PERFORATED METAL OF EVERY DESCRIPTION, FOR ALL USES.
225 NO. UNION ST CHICAGO, ILL.

SPECIAL MANUFACTURING.
DIES AND STAMPINGS TO ORDER.
SPEC'L MACHINERY-MODELS-EXPERIMENTAL WORK.
DROP FORGING DIES AND DROP FORGINGS.
HARDWARE SPECIALTIES ETC. MANF'D TO ORDER. SEND SAMPLES OR DRAWINGS FOR ESTIMATES. WRITE FOR OUR BOOKLET.
THE GLOBE MACHINE & STAMPING CO.
970 HAMILTON ST., CLEVELAND, OHIO.

ICE MACHINES, and Bottlers' Machinery. **Corliss Engines,** Brewers' THE VILTER MFG. CO., 899 Clinton St., Milwaukee, Wis

CHEMICAL EXAMINATIONS OF ALL KINDS.
DR. H. C. STIEFEL, Bissell Block. Pittsburgh. Pa.

MODELS & GEARS CATALOGUES FREE. UNION MODEL WORKS 193 CLARK CHICAGO.

MODELS & EXPERIMENTAL WORK.
Inventions developed. Special Machinery.
E. V. BILLAARD, Fox Bldg., Franklin Square, New York.

NOVELTIES & PATENTED ARTICLES
MANUFACTURED BY CONTRACT. PUNCHING DIES, SPECIAL MACHINERY.
E. KONIGSLOW STAMPING & TOOL WORKS, CLEVELAND, O.

Experimental & Model Work
Cir. & advice free. Wm. Gardam & Son, 45-51 Rose St., N.Y.

STEEL STAMPS—NAME PLATES
DIES & SHEET METAL WORK
PRESS WORK OF ALL KINDS
S. D. CHILDS & CO., 200 CLARK ST. CHICAGO.

Models and Experimental Work. Inventions and Models designed and perfected. Years of success. Modern shop. M. P. Schell, 517 Mission St., San Francisco

THE SCHWERDTLE STAMP CO.
STEEL STAMPS, LETTERS & FIGURES.
BRIDGEPORT CONN.

PATENT AND WORKING DRAWINGS.
G. M. MAYER, M.E., Monadnock Bl., Chicago, Ill.

ANY ONE CAN PRINT WITH THE MODEL PRESS
PRINTING

Full Course of Instructions in Printing Free
Over 50,000 Model Printing Presses Sold. Prints from a Card to a small Newspaper. IT'S NOT A TOY, IT'S A PRACTICAL PRINTING MACHINE. Highest Award at World's Fairs. Established 30 years. Send stamp for illustrated catalogue 272 at once. Prices $5.00 to $150.00. Every Press Guaranteed. MODEL PRINTING PRESS CO., 104-6 North 10th St., Philadelphia, Pa.

PUZZLE BOOKS
"Mental Nuts."—Can you crack 'em?
"Knots."—100 catch problems.
"1,400 Conundrums and Riddles."
"Great American Puzzle Book."
Real Brain Teasers, 10c. each; all 4 for 30c.
HOME SUPPLY CO., D-55, 132 Nassau St., New York

SETS OF CASTINGS OF MODEL ENGINES
SEND 10¢ FOR 126 PAGE ILL. CATALOGUE.
ALSO TOOLS, GEAR WHEELS & PARTS OF MODELS
GOODNOW & WIGHTMAN BOSTON
Removed to **132 Milk Street.**

Magical Apparatus.
Grand Book Catalogue. Over 700 engravings 25c. Parlor Tricks Catalogue, free.
MARTINKA & CO., Mfrs., 493 Sixth Ave., New York.

MASON'S NEW PAT. WHIP HOISTS
save expense and liability incident to Elevators. Adopted by principal storehouses in New York & Boston
Manfd. by VOLNEY W. MASON & CO., Inc.
Providence, R. I., U. S. A.

TYPEWRITERS ALL MAKES
All the Standard machines SOLD or RENTED ANY-WHERE at HALF MANUFACTURERS' PRICES. Shipped with privilege of examination. Send for Cat.
Typewriter Emporium, 203 LaSalle St., Chicago

50c. **DYNAMOS AND MOTORS** and all about them. By EDWARD TREVERT. 100 pages. Fully illustrated Catalog free. **BUBIER PUB. CO., Dept. S, Lynn, Mass.** **50c.**

THE NATURE LIBRARY is the only group of books on natural history that gives scientifically accurate information in simple narrative style, and in a way that makes it equally available for studious reference or casual entertainment.

It represents the first attempt made to illustrate a work of such magnitude and importance with direct photographic reproductions of living subjects of the animal, bird, fish, insect, and floral worlds in their native conditions. Additional to this photographic literalness, the fidelity to nature has been greatly heightened by color plates, which are so perfectly treated that the exact tint or tone of the living original is preserved through all the varieties of color. Thus the indentification of any bird, flower, moth, etc., is easy, and its classification becomes a matter of the utmost simplicity, an advantage of inestimable value to the student or general lover of nature hitherto perplexed and discouraged by old-fashioned so-called "keys."

This is the first time a systematic effort has been made to bring the reader into an intimate knowledge, free from fanciful invention, of the home life of our brethren of the lower world. The difficulties of photographing wild animals in their native environments, birds on their nests, and timid creatures in their hidings, are sometimes insuperable; but the success that rewarded the fatigues and hardships of the makers of THE NATURE LIBRARY, and which is attested throughout the pages of the ten beautiful volumes, makes this set of books not only unrivaled, but absolutely unique in the field.

Besides the 450 half-tones from photographs taken especially for this work in all regions of the country, and the 300 extraordinary and remarkably life-like color plates, there are about 1,500 text-cuts such as are usually regarded as all-sufficient illustrations of theses on natural history.

In the actual value of the pictorial matter, the purchaser gets more than the price of the ten volumes; and yet the information, charmingly, familiarly presented in the 4,000 pages, is a treasury from which the most careless reader may extract a sort of riches he would not willingly lose again.

But THE NATURE LIBRARY is not having careless readers. One point more frequently emphasized than any other by those who write in voluntary acknowledgment of their satisfaction with the purchase is the "entertaining" quality of the books.

Entertaining, they most unquestionably are—entertaining to old and young alike; and that was the great object aimed at by the makers of THE NATURE LIBRARY, who believe that the secret of all education is to make instruction entertaining and inspiring. We believe nothing better suited to the double purpose than these ten handsome and beautifully illustrated books has been offered to the public in many years.

COUNTRY LIFE IN AMERICA · DOUBLEDAY PAGE & CO 133-135-137 EAST 16TH ST. NEW YORK. · THE WORLD'S WORK ·

WE SHOULD LIKE TO SEND YOU postpaid, an elaborate booklet descriptive of THE NATURE LIBRARY and containing photo color-plates, black-and-white half-tones, specimen text pages, etc., with full particulars of the various styles of binding, prices, terms, etc. To avoid possible loss in the mails please write very plainly your name in full.

Your mail address, street and No. .....
Your City and State .....
A.S.O.

The Orient Surrey



Speed about twenty miles per hour. Will climb all ordinary grades.

Write for catalogue

WALTHAM MANUFACTURING CO.
Waltham, Mass.



CHARTER

GAS and GASOLINE
For All Work.
Stationaries, Portables, Hoisters, Pumpers, Sawing & Boat Outfits.
Send for Catalogue and Testimonials
State Your Power Needs.
CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

What Is Daus' Tip-Top?



TO PROVE that Daus' "Tip-Top" is the best and simplest device for making **100 copies** from pen-written and **50 copies** from typewritten original, we will ship complete duplicator, cap size, **without deposit**, on **ten (10) days' trial.**
Price $7.50 less trade discount of 33⅓ per cent, or $5 Net

The Felix A. B. Daus Duplicator Co., Daus Bldg., 111 John St., New York

---

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Safes, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.

Photo Lenses

and Shutters of every kind for all purposes; Professional, Amateur, Process.
Sold Round the World on all Cameras. Catalogue free.

Bausch & Lomb Opt. Co.

ROCHESTER, N. Y.
New York Chicago Boston

HOROLOGICAL DEPARTMENT

BRADLEY POLYTECHNIC INSTITUTE
Formerly Parsons Horological Institute
PEORIA, ILLINOIS
LARGEST and BEST WATCH SCHOOL in AMERICA



We teach Watch Work, Jewelry, Engraving, Clock Work, Optics. Tuition reasonable. Board and rooms near school at moderate rates.
Send for Catalog of Information.

Heals Cuts, Burns, Bruises, Sores, Etc.

CABOT'S Sulpho-Napthol

TRADE MARK
LIQUID CLEANLINESS.

At all dealers or 10c. and 25c. pkgs. by mail. Look for above trade mark.
Sulpho-Napthol Co., 15 Haymarket Square, Boston, Mass.
Sold in N. Y. City by Acker, Merrall, Macy, Siegel-Cooper.

CRUDE ASBESTOS

DIRECT FROM MINES

PREPARED ASBESTOS FIBRE for Manufacturers use

R. H. MARTIN,
OFFICE, ST. PAUL BUILDING
220 B'way. New York.

MAGIC LANTERNS

Stereopticons and Moving Picture Machines, all sizes, all prices. Views illustrating timely subjects. Fine thing for Church and Home Entertainments. Men with small capital **make money** giving public exhibitions. Illustrated catalogue free.
McALLISTER, MFG. OPTICIAN, **49 Nassau St., New York.**

UNIVERSITY SHOE

(Trade-Mark.)

Heaviest oily grain leather—tan colored. Watertight construction. Comfortable and nearly indestructible. Send for pamphlet.
J. P. TWADDELL,
1210-1212 Market St., Philadelphia



Crescent Machinery

Quality and Price both right

Band Saws, Jointers, Saw Tables, Band Saw Blades

Catalogue tells the rest

Crescent Machine Co., 230 Main Street, Leetonia, O., U. S. A.

JESSOP'S STEEL

THE VERY BEST
FOR TOOLS, SAWS ETC.
WM JESSOP & SONS Lᵗᵈ 91 JOHN ST. NEW YORK

OUR NEW SKELETON WATCH READY FOR DELIVERY OCTOBER 1st

New England WATCHES

An Ideal Christmas Gift

Our New Skeleton Watch not only shows you the time, but how time is made. Accurate time at that. Ready for delivery October 1st. For Sale by all Jewelers.
THE NEW ENGLAND WATCH CO., 37 & 39 Maiden Lane, New York
7 Snow Hill, London, England



The **Light Running YOST** is easy to operate.
Its **Beautiful Work** is easy to read.
Our **Unusual Catalogue** is easy to understand.

Why not send for the UNUSUAL CATALOGUE and learn of the BEAUTIFUL WORK done by the LIGHT RUNNING YOST? Sent free.

YOST WRITING MACHINE CO., 245 B'way, New York.

Every conscientious architect, builder and tin roofer, to say nothing of house owner, wants the best roof obtainable. Tin is better than all other kinds of roofing, and "Taylor Old Style" is better than any other kind of roofing tin.

A man with a house on his mind, whether he is architect, builder or owner, can learn something about tin as a roofing material that will be of lifelong value to him if he will ask for our book, "A Guide to Good Roofs," and a copy of "The Arrow."

N. & G. TAYLOR COMPANY

ESTABLISHED 1810
Philadelphia

CASTINGS IRON, BRASS & ALUMINUM

HIGHEST GRADE ONLY

We make a specialty of Cylinders, Casings, etc., and supply some of the most critical automobile and engine concerns. Send patterns or drawings for estimate. We guarantee satisfaction.

RACINE BRASS & IRON CO., Inc. - Racine, Wis.

WARREN'S

Natural Asphalt Sand Surfaced
ROOFING Apply it yourself. Makes a finished gravel roof. Comes ready to lay in rolls of 108 square feet. Write for sample, circular and prices.

Warren Chemical and Mfg. Co. 18 Battery Pl., New York

Olds Gas and Gasoline Engines

Perfect mechanical appliances make for absolute safety and economy.
Stationary Engines, 2 to 100 h. p.
Portable Engines, 8 to 18 h. p.

We have a new catalog, fully describing and illustrating our line, which will be sent on request.

OLDS GASOLINE ENGINE WORKS
216 River Street Lansing, Mich.

HAS NO SUPERIOR FOR HOISTING or HAULAGE.

"Patent Steel" Wire Rope

"PATENT STEEL" ROPE.

BRODERICK & BASCOM ROPE CO.
ST. LOUIS, MO.

THE MAN WHO KNOWS

the good and the bad points of all typewriters buys the

Remington

Remington Typewriter Co.
327 Broadway, New York

SMITH PREMIER TYPEWRITER

LIKE THE "MINUTE MAN" ALWAYS READY

500,000 satisfied users know this

Smith Premier Typewriter Co.

FACTORY AND HOME OFFICE SYRACUSE, N. Y.

Branch Offices or Representatives in every civilized country in the world

---

Proved Superiority

OF THE

Fox Typewriter

Do you realize it would be suicidal for us to make the broad claims we do for the Fox Typewriter unless we could prove them point by point in competitive tests with all other typewriters?

Seventy-five per cent. of our sales have been made under these trying conditions.

THE REASON WHY

It is in the mechanical construction pure and simple. The Fox is an *improved* machine built on the *only* lines that can be used *successfully* in typewriter construction—the lightest touch—unlimited speed—tabulator and two-color ribbon attachments, etc.—in fact, the most complete typewriter to be had at any price.

SEND FOR CATALOGUE.

FOX TYPEWRITER CO., Ltd.
Factory and Executive Office
826-840 Front St., Grand Rapids, Mich.

JEFFREY ELEVATING--CONVEYING--POWER

Transmission--Screening--Dredging--Coal Cutting
Drilling--Hauling--Washing Machinery.

For Catalogues address
THE JEFFREY MFG. CO.
Columbus, Ohio, U. S. A.
NEW YORK DENVER

Photographic illustrations for illustrating lectures on every subject, professional and popular.

SLIDES

The most complete library of illustration for every purpose at reasonable cost. Send for catalogue.

WILLIAM H. RAU, 1322 Chestnut Street PHILADELPHIA, PA.

CADILLAC



Model K.
Complete, $900.
Without Tonneau, $800.

Ease of Control

No other automobile is so easy to manage as a Cadillac. Simple mechanism, powerful brake, reliable, noiseless speed gear, and accurate steering apparatus make the Cadillac an easily controlled car at all times, and under all conditions.

Cadillacs cost $750 to $900. You may pay more for others not so efficient.

Write for booklet N which tells all about Cadillacs and gives address of nearby agency where they may be seen and tried.

CADILLAC AUTOMOBILE CO., Detroit, Mich.
Member Association of Licensed Automobile Manufacturers.

"Temple-Clasps"

FIRE Away Those Nose Pinchers **STOP** Pinching Your Thinking Apparatus

And let us fit you perfectly **BY MAIL**

A postal will bring our beautiful FREE CATALOGUE with full explanation as to how we will positively guarantee to give you the best Eye Help in the world.

BRIGGS OPTICAL CO.
344 B. Triangle Building Rochester, N. Y.



ELECTRICAL TRAINS TROLLEY CARS DYNAMOS NOVELTIES

THE CARLISLE & FINCH CO
233 E. CLIFTON AVE
CINCINNATI, O.

WRITE FOR CATALOGUE "B"

THE "BEST" LIGHT

Spectacles and Eyeglasses

are a superfluity where our lamps are used.

Portable, 100-candle power and produces a safe, white, powerful, steady light with

No odor, dirt, grease or smoke.

Every lamp warranted. Costs 2c per week.

AGENTS WANTED EVERYWHERE.

The BEST LIGHT CO.
Owners of Original Patents.
87E. 5th St., Canton, O.

THE FRANKLIN MODEL SHOP

Inventors, amateur machinists, schools and colleges furnished with anything in metal from a simple plane to a complete working model. Drawings and designs worked out from inventors' ideas. Write for estimates. Send for booklet No. 3, free.

PARSELL & WEED, 129-131 W. 31st St., New York

MILLS FOR ALL MATERIALS.



OUR BUSINESS IS TO MAKE MACHINERY FOR GRINDING GRAIN, CRUSHING ROCKS AND PULVERIZING ALL HARD SUBSTANCES. WE HANDLE ALL KINDS OF MATERIALS FROM COTTON-SEED TO ROOTS AND HERBS, BY AN UNEXCELLED PROCESS. IF YOU WANT ANY KIND OF A MILL OR GRINDING MACHINE, COME TO US AND YOU WILL GET THE BEST AND STILL SAVE MONEY.

DEAL WITH US ONCE AND YOU WONT CHANGE.

ESTIMATES FREELY FURNISHED.

SPROUT, WALDRON & CO.
(SEND FOR CATALOG No 4.) MUNCY, PA.

HEIMET OIL LUBRICATES ANYTHING.

IF YOU HAVE A HOT BOX TRY IT. C. H. BESLY & CO. CHICAGO, ILL. U.S.A.

15 to 21 Clinton Street.

"LIGHTWEIGHT" PRESIDENT SUSPENDERS

mean freedom in breathing. Weigh 2 oz. **Any store 50c** and $1.00 postpaid for choicest patterns.

THE C. A. EDGARTON MFG. CO., Box 810, Shirley, Mass.